



# Warrington Borough Council Carbon Management Programme

Five Year Carbon Management Plan 2010-2015

February 2011



*working together*

## Contents

<b>Foreword from Diana Terris and Councillor Mike Biggin</b>	<b>3</b>
<b>Foreword from the Carbon Trust</b>	<b>4</b>
<b>Management Summary</b>	<b>5</b>
<b>1 Introduction</b>	<b>8</b>
<b>2 Carbon Management Strategy</b>	<b>9</b>
2.1 Context and drivers for Carbon Management	9
2.2 Targets and objectives	9
<b>3 Emissions Baseline and Projections</b>	<b>11</b>
3.1 Scope	11
3.2 Carbon Baseline	12
3.3 Display energy certificates	13
3.4 Projections and Value at Stake	14
<b>4 Carbon Management Projects</b>	<b>16</b>
4.1 Project Delivered between April 2009 and April 2011	16
4.2 Planned / funded projects	18
4.3 Unfunded and Aspirational	20
4.4 Projected achievement towards target	23
<b>5 Carbon Management Plan Financing</b>	<b>24</b>
5.1 Assumptions	24
5.2 Benefits / savings	24
5.3 Financial costs and sources of funding	25
<b>6 Actions to Embed Carbon Management in the Organisation</b>	<b>27</b>
6.1 Corporate Strategy – embedding CO <sub>2</sub> saving across Warrington Borough Council	28
6.2 Programme Management – bringing it all together effectively	28
6.3 Responsibility – being clear that saving CO <sub>2</sub> is everyone's job	29
6.4 Data Management – measuring the difference, measuring the benefit	30
6.5 Communication and Training – ensuring everyone is aware	30
6.6 Finance and Investment – the money to match the commitment	32
6.7 Policy Alignment – saving CO <sub>2</sub> across our operations	32
6.8 Engagement of Schools – working with Schools to reduce their carbon footprint	33
<b>7 Programme Management of the CM Programme</b>	<b>34</b>
7.1 The Programme Board – strategic ownership and oversight	34
7.2 The Climate Change Implementation Group – delivering the projects	35
7.2 Succession planning for key roles	36
7.3 Ongoing stakeholder management	36
7.4 Annual progress review	38
<b>APPENDIX A: Value at Stake Scenarios</b>	<b>39</b>
<b>Appendix B: Carbon Management Matrix – Embedding</b>	<b>41</b>
<b>Appendix C: Highlight Report</b>	<b>43</b>
<b>Appendix D: Definition of Projects</b>	<b>45</b>

Building and Engagement Projects (including schools)  
Business travel  
Fleet  
Waste  
Water  
Street lighting  
Renewable Technologies

## Figures

Figure 1 Breakdown of emissions for Warrington Borough Council for baseline year .....	5
Figure 2 Salix funded solar bollard .....	8
Figure 3 The 5 step process of the local authority carbon management programme .....	8
Figure 4 Our buildings DEC ratings (Oct 2010) .....	9
Figure 5 Sectors included in our carbon footprint .....	11
Figure 6 Numbers of buildings per DEC rating as of October 2010 .....	13
Figure 7 DEC ratings versus carbon emissions of WBC buildings.....	13
Figure 8 The Value at Stake between acting and achieving our carbon reduction target of 40%, and continuing as usual .....	15
Figure 9 Planned progress towards our carbon reduction target .....	23
Figure 10 The Salix recycling fund process .....	25
Figure 11 Salix recycled fund financing .....	26
Figure 12 Carbon Management Matrix scores at the start of the plan and our targets for end score .....	27
Figure 13 Value at Stake for Schools .....	33
Figure 14 Organisational context of carbon management programme .....	34
Figure 15 Organisational chart for carbon management programme .....	35

## Tables

Table 1 Summary of carbon and financial benefits of the carbon management programme .....	6
Table 2 Funding and investment required within plan.....	7
Table 3 Summary table of emissions for Warrington Borough Council for baseline year 2009/10 .....	12
Table 4 Value at Stake for different emissions reductions over the next 5 years.....	14
Table 5 Representation of the Value at Stake graph .....	15
Table 6 Projects undertaken between April 2009 and April 2011 .....	16
Table 7 Funded projects for April 2011 to March 2015.....	18
Table 8 Unfunded/aspirational projects for April 2011 to March 2015 .....	20
Table 9 Renewable technology projects for April 2011 to March 2015.....	22
Table 10 Quantified Benefits and Savings of all projects.....	24
Table 11 Financial costs of projects in plan .....	25
Table 12 Succession planning for key roles in Warrington Borough Councils carbon management plan.....	36
Table 13 The climate change communications plan .....	37
Table 14: Value at stake scenarios (figures are cumulative value at stake over 5 years).....	39


## Foreword from Diana Terris and Councillor Mike Biggin

Warrington Borough Council is determined to guide our community and lead Warrington to a sustainable, low-carbon future which will ensure that residents, visitors and businesses choose Warrington as a preferred location in which to live, work and invest. The challenges are significant but we are committed to leading the way.


Our growth and prosperity in the past was supported by affordable energy which gave rise to emissions of carbon that are now causing our climate to change. Some of these effects have already been seen in Warrington with extreme weather events such as high winds and flooding in recent years. Our challenge for the future will be to prosper as a community in a low carbon way. Now is an ideal time to seize the opportunity to reduce our emissions and make cost savings in the process.

Warrington Borough Council's Sustainable Community Strategy sets us a carbon reduction target of reducing the borough's carbon emissions by 40% from 2006 levels by 2030. In 2007 we produced our Climate Change Strategy which started us on our mission to embed carbon reduction across the council. We must all play our part in making deep reductions in carbon emissions and this Carbon Management Plan is the first step in the Council's journey to set a low carbon example.

This plan will be used to identify opportunities for emissions reductions, monitoring our improvements and ensuring that carbon emissions and energy efficiency are at the centre of Warrington's strategies going forward. This challenge is significant but we are confident that employees of Warrington Borough Council will pull together and help us achieve this ambitious plan, setting an example that the rest of the community and the sector will follow enthusiastically.



Diana Terris  
Chief Executive  
Warrington Borough  
Council



Cllr Mike Biggin  
Executive Board Member for  
Climate Change and Public  
Protection

All Executive Directors have signalled their full support for the ambitions and objectives within this Plan.



## Foreword from the Carbon Trust

Cutting carbon emissions as part of the fight against climate change should be a key priority for all public sector organisations. Carbon management is about realising efficiency savings, transparency, accountability and leading by example. The UK government has identified the public sector as key to delivering carbon reduction across the UK in line with its Climate Change Act commitments and the Local Authority Carbon Management Programme is designed in response to this. It helps organisations to save money on wasted energy and put it to better use in other areas, while making a positive contribution to the environment by lowering carbon emissions.

Warrington Borough Council partnered with the Carbon Trust on this programme in 2010 to realise the substantial carbon and cost savings. This Carbon Management Plan commits Warrington Borough Council to a target of reducing CO<sub>2</sub> by 40% by 2015 and underpins potential financial savings and cost avoidance to the organisation of around £10 million by that date.

Public sector organisations can contribute significantly to reducing CO<sub>2</sub> emissions and improving efficiency. The Carbon Trust is therefore very proud to support Warrington Borough Council in their on-going implementation of carbon management.



Richard Rugg  
Head of Public Sector, Carbon Trust



## Management Summary

### Headlines

**In 2009 / 2010 Warrington Borough Council was responsible for emitting 34,737 tonnes of carbon costing the authority £7 million a year**

**We have set an aspirational target to reduce these emissions by 40% by April 2015**

**The difference between taking action to achieve this target and doing nothing is more than £10 million over 5 years**

This carbon management plan will help Warrington Borough Council to focus its strategies and policies towards mitigating the effect of climate change from April 2010 until March 2015. Saving carbon means that we will save energy and therefore money, which will assist in the council's budget challenges and the efficiency savings that the council is undergoing.

The climate change programme is part of the Transforming Warrington agenda and thus has a high profile within the authority.

We have begun to embed climate change into our procedures and decision making to ensure that we meet the targets that are set by our government. We want to lead our community in a responsible attitude towards responding to the threat of climate change.

Action by local authorities will be critical to the achievement of the Government's climate change objectives, such as the long term goal to reduce CO<sub>2</sub> emissions by 80% by 2050, as set out in the Climate Change Act.

The carbon management plan will support Warrington's climate change strategy which was produced in 2007. The carbon management plan is a strategic way forward for the authority to deliver carbon reduction of its own emissions.

Our emissions in 2009/2010 were as shown in **Figure 1**; our carbon footprint is 34,737 tonnes. The graph shows that the main areas for us to focus on are schools and streetlighting which together make up 60% of our emissions.




Figure 1 Breakdown of emissions for Warrington Borough Council for baseline year

The incentive to reduce our emissions is driven by:

- **Financial reasons:**  
Assisting in the council’s cost saving efforts  
Anticipating saving money from the carbon reduction commitment
- **Environmental reasons:**  
Sustainable use of resources  
Action on climate change
- **Political and social reasons:**  
Boosts the council’s green credentials  
Supporting and acting as a leader to the residents and businesses of the borough

We have set an aspirational target reduction of 40% of our 2009/2010 emissions by April 2015. The difference between taking action to achieve this target and doing nothing is more than £10 million over 5 years. As well as the environmental benefits, there is a clear financial incentive to act now.


	2009/2010	2010 / 2011	2011 / 2012	2012 / 2013	2013 / 2014	2014 / 2015
<b>Annual cost saving</b>	<b>£38,694</b>	<b>£137,686</b>	<b>£945,879</b>	<b>£1,484,885</b>	<b>£1,903,248</b>	<b>£2,044,169</b>
<b>Annual CO<sub>2</sub> saving</b>	<b>229.74</b>	<b>757.62</b>	<b>4827.76</b>	<b>7804.52</b>	<b>10369.09</b>	<b>11249.60</b>

Table 1 Summary of carbon and financial benefits of the carbon management programme

**To achieve our target we are looking to:**

- Directly reduce our emissions
- Embed the consideration of carbon
- Invest to save carbon and save money
- Raise awareness amongst staff
- Form a partnership with schools to address their energy use

The plan identifies projects that will achieve a reduction of 11,515 tonnes; or 33% of our carbon footprint. Over the next five years we will annually review our progress and continue to identify further projects that will help us achieve our target.



To achieve our reduction we will need to change some policies and procedures but we will also need to invest to save. **Table 2** shows how much we would need to invest within our programme timescale and beyond. Some of this funding has been approved and we will need to seek further funding for some projects.

	2010/11	2011/12	2012/13	2013/14	2014/15	Ongoing
<b>Already spent</b>	<b>£884,639</b>					
<b>Funding for approved projects</b>		<b>£417,081</b>	<b>£323,081</b>	<b>£323,081</b>	<b>£323,081</b>	<b>£1,500,000</b>
<b>Funding needing to be sourced</b>		<b>£46,000</b>	<b>£1,225,498</b>	<b>£141,383</b>	<b>£26,383</b>	<b>£2,120,000</b>
<b>Renewable Technology funding to be sourced</b>		<b>£3,000,000</b>	<b>£7,000,000</b>	<b>£1,000,000</b>	<b>£1,000,000</b>	<b>£3,000,000</b>

Assumptions are prices correct at 2010/11 and do not include inflation

*Table 2 Funding and investment required within plan*

The carbon management plan will be promoted by the climate change team and climate change board who will work with the climate change implementation group to deliver and identify projects. If we are to achieve our ambitions, we will need every member of staff to understand the need to save energy and the ways that they can help.

The actions and results of the climate change programme will be reported into our senior management teams and into performance indicators. Our carbon footprint will be calculated annually, with actions being reported and recorded quarterly.



# 1 Introduction

In May 2010 Warrington Borough Council joined the Carbon Trust local authority management programme. This provided us with 10 months of technical and organisational change support to give greater focus to the climate change programme in Warrington Borough Council.



Prior to the programme we had produced our Climate Change Strategy in 2007 and developed a good understanding of our emissions. Through Salix funding in early 2010 we improved our street lighting assets and identified energy efficiency measures to improve some of our buildings.

We really needed to start to identify where we could implement big projects that would impact on our emissions and embed carbon management in the ethos of our organisation. The Carbon Trust programme has given us the opportunity to do this.

Figure 2 Salix funded solar bollard

The programme has guided Warrington Borough Council through the 5 steps outlined in **Figure 3**.




Figure 3 The 5 step process of the local authority carbon management programme

Through the steps undertaken on the programme we have scrutinised our emissions and identified where we can make changes over the next 5 years and make a significant impact.

The benefits of producing and implementing this plan are:

- Acting to protect our environment
- Working towards reducing our environmental impacts and carbon emissions
- Reducing our energy costs
- Complying with legislation
- Leading the way and demonstrating best practice

The rest of this plan describes in detail our strategy, our emissions and the projects and steps that we will take to successfully reach our carbon reduction target. The plan looks at our progress from April 2010 and our plans till March 2015.

## 2 Carbon Management Strategy

The carbon management strategy outlines our drivers, our targets for carbon reduction and our strategy for achievement over five years.

### 2.1 Context and drivers for Carbon Management

Human activities are increasing the amount of greenhouse gases in our atmosphere to dangerous levels that are causing climate change and impacting upon our world. This is a global issue which we all have a part to play in combating.

The UK Government has placed an emphasis on local authorities setting an example and taking a leading role in taking action on Climate Change. Action by local authorities will be critical to the achievement of the Government's climate change objectives, such as the long term goal to reduce CO<sub>2</sub> emissions by 80% by 2050, as set in the Climate Change act.

Rating	Number of DECs
A	0
B	4
C	4
D	41
E	34
F	6
G	20

The act has resulted in a number of legislative drivers for local authorities:

- Display Energy Certificates:** As of 1 October 2008 there has been a legal requirement for all public sector buildings with a total floor area of over 1,000m<sup>2</sup>, to show a Display Energy Certificate (DEC) in a prominent place, clearly visible to the public. The majority of our buildings are below the average C/D rating.
- Carbon Reduction Commitment:** As of April 2012, we will pay £12 per tonne for the carbon that we emit. The CRC scheme will cost Warrington Borough Council around £390k a year. This additional cost will help to justify the case for carbon saving.

Figure 4 Our buildings DEC ratings (Oct 2010)

As well as reducing the costs we pay through the carbon reduction commitment, measures to increase energy efficiency will reduce energy costs, which is particularly important for the future given both the predicted increases in and the continued volatility of energy prices. Energy and fuel costs have seen a dramatic rise in recent years, with energy prices increasing by well over 50% since 2004. This trend is not expected to change and we must accept that the price we pay for our energy will continue to increase in the coming years.

As budgets have been reduced due to the current financial situation, the need for efficiency and cost saving is even more important. Carbon saving programmes that aim to reduce energy and fuel usage will also result in cost savings, helping ease budget cuts and assist in efficiency savings.

As a council we have signed the Nottingham Declaration, declaring our commitment to assess our emissions and to reduce them. The climate change programme is part of Transforming Warrington; this programme is a high profile agenda in the council for major change projects. This helps to embed carbon management across our whole organisation.

All of these factors are driving us as an authority to reduce our carbon emissions.

### 2.2 Targets and objectives

The climate change board have set an aspirational target reduction of 40% of our 2009/2010 emissions by April 2015.

This is considerably more ambitious than previous targets, reflecting the increasing urgency of making deep cuts in carbon emissions to meet UK and global requirements.

## Carbon Reduction Target

We have set an aspirational target to reduce our 2009/10 carbon emissions by 40% by April 2015.

During development of this carbon management plan, we have identified carbon reduction projects that are predicted to reduce our carbon emissions by 33%. These projects are discussed in section 4. During the five year duration of the plan, we will be reviewing our projects on a regular basis and tracking our progress against our target at least annually, to coincide with publishing our annual carbon footprint report.

We are confident that with the support of all Warrington staff, we will continue to identify projects to help us achieve the full target within the programme plan.

### 2.3 Strategic themes

To achieve our goals we will work towards the following themes.

- **Directly reducing our emissions:** the main areas where we seek to reduce emissions are through our schools, our fleet and our street lighting; these are the areas where there is the greatest room for improvement
- **Embedding the consideration of carbon:** we intend to ensure that our policies and procedures consider the impacts on or of climate change and amend policies to consider impact on emissions where possible
- **Investing to save carbon and save money:** we will seek to increase the amount of funding for invest to save projects so that the council can pursue its carbon reduction target
- **Raising awareness amongst staff:** Communicating the importance of carbon reduction to all our staff and making them aware of our progress
- **Form a partnership with schools to address their energy use** Schools account for 40% of Warrington Borough Council's carbon footprint. They are our hardest engagement area because their energy and asset management processes are often complex. Overcoming these difficulties to form an effective partnership with schools will feature heavily in our plans.

### 3 Emissions Baseline and Projections

This section describes how we calculated our carbon footprint and breaks down for the reader where our carbon emissions come from and the potential for significant carbon savings.

In 2009/10 Warrington Borough Council was responsible for the emission of 34,737 tonnes of CO<sub>2</sub> costing the organisation around £7 million

#### 3.1 Scope

To develop our baseline and measure our carbon footprint we have included:

- Electricity consumption from our buildings and street lighting
- Gas and oil consumption from our buildings
- All staff business travel (by car, plane and train)
- Our fleet’s fuel consumption (petrol, diesel and gas oil)
- Water consumption from our buildings
- Waste produced from council buildings




Figure 5 Sectors included in our carbon footprint and those we wish to incorporate in the future

This has been based on what we are required to report for the carbon reduction commitment, what we previously reported for the expired National Indicator 185 and what other information we were able to collate.

Areas that have not been included in this scope:

- **Warrington Borough Transport fleet fuel usage:** We want more people to use the public transport network in Warrington, focusing on reducing the carbon emissions per passenger. Therefore overall fuel usage may remain fairly static; this is monitored through the climate change implementation group.

- **Golden Gates Social Housing:** Since starting this programme a stock transfer has taken place and Golden Gates are now entirely independent from the council. They are developing their own energy reduction strategy.
- **Outsourced activities from our care providers:** We aim to work with our providers in the future to ensure they all monitor their emissions to allow us to fully declare ours.
- **Staff commuting:** The last staff travel survey was completed in 2007. This information is out of date therefore we have not included it. We have a travel to work policy and are looking to improve our understanding of commuting and include this in our scope at a later date.
- **Refrigerants:** Refrigerant usage is not significant at Warrington Borough Council and there are therefore no consistent records of usage. This will be monitored.

### 3.2 Carbon Baseline

We have used the financial year 1<sup>st</sup> April 2009 to 31<sup>st</sup> March 2010 as our baseline year.

**Table 3 and figure 1** show the source of our emissions. Our carbon footprint for 2009/2010 is 34,737 tonnes.

The largest portion of our emissions comes from our schools which account of 40% of our carbon footprint.

Setting the baseline for 2009/2010 just before the authority started going through a significant organisational change, provided us the opportunity to propose our changes alongside this.

Because of the organisational changes that are taking place it will be important to note the emissions per employee. As of the 31<sup>st</sup> March 2010 there were 8,912 people employed by the council (including teachers) making emissions per employee 3.9 tonnes.

	CO <sub>2</sub> (tonnes)	%
<b>Buildings and street lights</b>	31,696	91%
<b>Transport</b>	2,635	8%
<b>Housing</b>	-	0%
<b>Further scope</b>	407	1%
	<b>34,737</b>	<b>100%</b>

Table 3 Summary table of emissions for Warrington Borough Council for baseline year 2009/10




Figure 1 Breakdown of emissions for Warrington Borough Council for baseline year

### 3.3 Display energy certificates

The Display Energy Certificate or DEC's can be used to show how energy efficient our buildings are. As you can see in **Figure 6** most of our buildings that hold DEC's are below average (under C), in some cases because they have high emissions and others because they have equipment like oil fired boilers.

**Figure 7** shows that most of our buildings use less than average amounts of energy and it is just a small number of buildings that are using a lot of energy. We have an audit programme of our buildings to investigate where their energy consumption can be improved.




Figure 6 Numbers of buildings per DEC rating as of October 2010




Figure 7 DEC ratings versus carbon emissions of WBC buildings

### 3.4 Projections and Value at Stake

The 'value at stake' is the potential cost saving of achieving our target compared to taking no action.

To look at the value at stake we have investigated our consumption and energy costs. At this stage we cannot be sure how energy prices or our use of energy will rise in the future, therefore for this section of the plan we have created a number of 'scenarios' which make different assumptions. For this plan we have used a central scenario which is described below. A full set of the scenarios we considered can be found in Appendix A.

If business continued as usual (we did nothing more to reduce our emissions) for Warrington Borough Council we have predicted that our consumption would increase by 0.7% per year. Previously our consumption has risen by around 2% per year. With the current economic downturn and limits to available funding, our staff will be reducing but this might not result in direct reductions in energy use. There are a few key projects that will add to our footprint such as the Orford Park development, so a small increase is required to account for this.

The assumptions we have worked with for our business as usual scenario are:

- Increase consumption of 0.7% per year (Consumption growth in line with nationally published figures from BERR)
- Increase in energy and fuel prices of 1.7% per year (Increase in unit costs in line with DECC 'central' scenario for electricity for 'services', averaged for 2009 -2014)

If we were just to keep our emissions as they were and just reduce by the predicated yearly consumption increases the council would save £870k over the 5 years of this plan.

The value at stake for a number of emissions reductions over the next 5 years is shown **Table 4**.

These scenarios give us a clear financial incentive to act and deliver our carbon management plan. The value at stake does not include the cost of the projects we will implement to achieve this target; these will be outlined later in section 4 and 5 of the document.

Reduction	Value at Stake (Cumulative over 5 years)
10%	£2,998,410
20%	£5,289,314
30%	£7,660,782
40%	£10,130,948

Table 4 Value at Stake for different emissions reductions over the next 5 years

If we do reduce our emissions by our target of 40%, the value at stake for Warrington Borough Council is just over £10 million over the next 5 years. This is illustrated in **Figure 8**. The business as usual (BaU) line with no action taken is the upper line. The lower line is where we would like to be. The value at stake is the difference between these two lines cumulatively over the five years.




Figure 8 The Value at Stake between acting and achieving our carbon reduction target of 40%, and continuing as usual

	2010/2011	2011/2012	2012/2013	2013/2014	2014/2015
<b>Yearly Value</b>	£ 727,593	£ 1,413,239	£ 2,060,791	£ 2,673,798	£ 3,255,528
<b>Cumulative Value</b>	£ 727,593	£ 2,140,831	£ 4,201,622	£ 6,875,420	£ 10,130,948

Table 5 Representation of the Value at Stake graph



## 4 Carbon Management Projects

The above statement makes clear how much carbon we have currently identified through a number of projects. The following sections will highlight those projects that have been delivered and the projects that we wish to deliver over the next 5 years.

The current carbon reduction projects identified represent a 33% reduction of our baseline. Whilst the current projects do not account for our full 40% reduction, we will endeavour to achieve it, continuing to identify carbon reduction projects as our situation changes. We will annually update our project sheets and make them publicly available.

Further detail about the projects listed in 4.2 and 4.3 can be found in appendix D.

### 4.1 Project Delivered between April 2009 and April 2011

The projects that have been delivered between April 2009 and April 2011 are highlighted in **Table 6**.

Projects 1, 3, 5 and 11 are part of regular maintenance programmes or were undertaken to improve efficiencies in the council.

Projects 2, 4, 6 – 10, 12 & 14 have been funded through a £250k loan fund from Salix Finance which was matched by another £250k from the council. The financial savings will be recycled back into an invest to save fund that will enable further investment in energy efficiency. The details of this fund are described in section 5.

Project 13 was funded by a £268k interest free loan from Salix that we did not need to match fund and we will not be able to recycle.

*Table 6 Projects undertaken between April 2009 and April 2011*

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
<b>Building Programmes (Including Schools)</b>								
1	Palmyra Square Building Closure	Stewart Brown	£0		£38,694	229.7	0.0	2009 / 2010
2	Voltage optimisation for 3 sites	Mark McGivern	£79,501 (C)		£19,159	104.3	4.1	2010 / 2011
3	Boiler Controls: Ensuring they are set correctly	Elwyn Rowlands	part of regular maintenance		£29,005	210.5	0.0	2010 / 2011
4	Broomfields Leisure – Variable Speed Drives	Mark McGivern	£4,544 (C)		£1,200	6.5	3.8	2010 / 2011
5	Great Sankey Leisure – Variable Speed Drives	Mark McGivern	£6,210 (C)		£1,700	9.3	3.7	2010 / 2011

Ref	Project	Lead	Cost	Annual Savings (yr 1)		Pay back (yrs)	Implementation Year	
				Capital (C) Operational (O)	Financial (Gross) tCO <sub>2</sub>			
6	Replacement of Broomfield Junior Schools oil fired boiler	Hilary Smith	based on maintenance		£3,558	19.4	N/A	2010 / 2011
7	Woolston Leisure – Variable Speed Drives	Mark McGivern	£4,544 (C)		£1,200	6.5	3.8	2010 / 2011
8	Great Sankey Leisure / High – Voltage optimiser	Mark McGivern	£30,000 (C)		£8,409	45.8	3.6	2010 / 2011
9	Lymm High – Building Management System	Mark McGivern	£10,000 (C)		£3,266	26.1	3.1	2010 / 2011
10	Lymm High – Voltage optimisation	Mark McGivern	£33,000 (C)		£8,409	45.8	3.9	2010 / 2011
11	New Town house – Voltage optimisation	Mark McGivern	£18,000 (C)		£4,365	23.8	4.1	2010 / 2011
<b>Fleet</b>								
12	Fleet Efficiencies	David Smith	£38,000 (C)		£1,772	4.1	*	2010 / 2011
<b>Street lighting</b>								
13	Street lighting and bollards	Dave Vasey	£393,000 (C)		£56,128	305.4	7.0	2010 / 2011
14	Street lighting and bollards 2	Dave Vasey	£267,840 (C)		£59,938	326.2	4.5	2010 / 2011
<b>Totals</b>			<b>£884,639</b>		<b>£236,803</b>	<b>1363.4</b>	<b>N/A</b>	<b>N/A</b>

\* Payback based avoiding external costs

## 4.2 Planned / funded projects

From the Salix financing we received in 2010, we will have an invest to save 'pot' created from recycled funds that will be ring fenced for projects that payback within 5 years.  
Project 31, the fleet electric vehicle has been funded by a DEFRA air quality grant.

We will also be receiving capital investment each year of £250k for invest to save projects. The projects outlined below will either be funded through the above, or create desirable efficiencies for the department on a cost basis or are relatively cost free (e.g. awareness raising) but will require policy changes or staff time.

Operational costs for building programmes have not been included as we have an internal building maintenance team that maintain systems as part of existing programmes. Operational costs are only included in new exceptional circumstances.

Table 7 Funded projects for April 2011 to March 2015

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
<b>Building and Engagement Projects (Including schools)</b>								
15	5 Tanning Court – Voltage optimisation	Mark McGiverson	£24,000 (C)		£6,387	34.8	3.8	2010 / 2011
16	St Margaret's Primary Rationalisation	Hilary Smith	Done for efficiencies		£12,495	73.2	N/A	<b>2011/2012</b>
17	Rationalisation of Bruche Primary	Hilary Smith	Done for efficiencies		£6,952	44.7	N/A	<b>2011/2012</b>
18	Rationalisation of Pupil Referral Unit	Hilary Smith	Based on maintenance		£39,702	266.3	N/A	<b>2011/2012</b>
19	New Build Chapelford Primary	Hilary Smith	Based on maintenance		£2,778	27.9	N/A	<b>2011/2012</b>
20	New Build Great Sankey Primary	Hilary Smith	Based on maintenance		£5,489	52.2	N/A	<b>2011/2012</b>
21	Schools Engagement Program	Hilary Smith	£500 (O)		£106,967	674.3	0.0	<b>2011/2012</b>
22	Engagement: Eco-rep in each team	Laura Stanley	£500 (O)		£69,893	380.3	0.0	<b>2011/2012</b>
23	Insulation: Flange and Value Insulation	Mark McGiverson	£117,849 (C)		£27,105	216.8	4.3	<b>2011/2012</b>
24	Broomfields Leisure –Building Management	Mark McGiverson	£18,000 (C)		£2,967	23.7	6.1	<b>2011/2012</b>

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
	System							
25	5 year building rationalisation	Stewart Brown		Based on Efficiencies	£33,214	204.8	N/A	<b>2014/2015</b>
26	Audits 7: 3 High School Energy Audits	Mark McGivern	£32,230 (C)		£37,787	232.9	Variable due to a number of different projects the majority payback within 5 years	These programmes will be implemented from April 2011 to March 2015 dependent on paybacks and funds available
27	Audits 1	Mark McGivern	£140,500 (C)		£36,620	257.3		
28	Audits 3: 20 schools energy audits	Mark McGivern	£155,705 (C)		£40,435	288.2		
29	Audits 5: 12 schools energy audits & 1 recreation ground	Mark McGivern	£31,317 (C)		£8,375	59.1		
30	Audits 6	Mark McGivern	£356,000 (C)		£97,883	660.1		
31	Audits 2	Mark McGivern	£94,000 (C)		£24,846	151.7		
32	Audits 4: 39 schools energy audits	Mark McGivern	£147,686 (C)		£38,420	273.7		
33	Audits of libraries and C	Mark McGivern	£108,708 (C)		£35,756	221.3		
<b>Business Travel</b>								
33	Package of Business Travel options	Steve Hunter / Ben Logan	£1,400 (C) £1,070		£75,767	168.9	0.0	<b>2012/2012</b>
<b>Fleet</b>								
35	Telematic System for Fleet	David Smith	£70,000		£58,043	133.9	1.2	<b>2011/2012</b>
36	Fleet electric vehicle	Rachel Waggett	£29,000 (C)		£1,205	2.8	Long Term Project	<b>2011/2012</b>

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
<b>Waste</b>								
37	Corporate Waste Minimisation Strategy and implementation	Paul McHenry	N/A due to contracts		31.7 tCO <sub>2</sub>	N/A	2011	2011/2012
<b>Water</b>								
38	Water 1: Save a Flush	Laura Stanley	£2,000 (C)		£18,934	3.2	0.1	2012/2013
<b>Totals</b>			<b>£1,388,395</b>		<b>£788,100</b>	<b>4,484</b>	<b>N/A</b>	<b>N/A</b>

### 4.3 Unfunded and Aspirational

The following projects are ones that we hope to achieve over the next 5 years.

These are projects that we need to seek funding for or are of an aspirational nature that we would need to seek approval for or need to consult the public on.

We anticipate that this funding gap will be met by identification of external sources of funding, such as intermittent interest free loans and grants released by central Government.

Table 8 Unfunded/aspirational projects for April 2011 to March 2015

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
<b>Building and Engagement Projects (Including Schools)</b>								
39	Boilers: Oil to gas boiler Conversion	Elwyn Rowlands / Hilary Smith	£1,690,000 (C)		£80,508	453.4	17.7	Ongoing
40	Boilers 2: Oil to biomass boiler Conversion	Elwyn Rowlands / Hilary Smith	£430,000 (C)		£27,935	273.1	15.4	Ongoing
41	Insulation 2: Cavity and loft insulation for schools	Mark McGivern	£1,004,498 (C)		£68,941	551.4	14.6	2012/2013
42	Bus Interchange: Lighting Replacement	Mark McGivern	£46,000 (C)		£5,385	29.3	8.5	2011/2012

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
43	Dedicated resource schools / energy management	Hilary Smith / Rachel Waggett	£26,383 (O)		£106,967	674.3	0.0	2013/2014
<b>Fleet</b>								
44	Fleet Replacement Strategy of RCV's	David Smith	Based on maintenance		£161,207	372.9	0.0	2011/2012
<b>Street Lighting</b>								
45	Street Lighting Bollard Replacement	Dave Vasey	£106,000 (C)		£15,341	83.5	6.9	2012/2013
46	Street Lighting Lantern Change Mercury Vapour Lamps	Dave Vasey	£117,000 (C)		£31,283	170.2	3.7	2012/2013
47	Street Lighting Part Night Operation	Dave Vasey	£0		£311	1.7	0.0	2014/2015
48	Column Removal	Dave Vasey	£0		£1,263	6.9	0.0	2013/2014
49	Street Lighting Sign Lantern Replacement	Dave Vasey	£115,000 (C)		£26,089	142.2	4.4	2013/2014
<b>Totals</b>			<b>£3,574,517</b>		<b>£525,230</b>	<b>2,759</b>	<b>N/A</b>	<b>N/A</b>

#### 4.4 Renewable Technologies

There are a number of reasons that renewable technologies have been separated out from the other projects. They are not as simple as invest to save and require more explanation.

The high cost of these projects would require the council to borrow finance to fund them. The figures below are estimates and do not include the additional costs of paying back the interest on the finance.

The savings do not show the income that is gained from the feed in tariff for renewable technology. This gives you a payment per kWh of energy produced. These large scale projects would create extra income from this feed in tariff, reducing payback periods and providing a long term income after this.

The solar farm project would also need public consultation as well as internal council approval and external financing.

This are all projects we wish to implement to show our commitment to reducing our emissions and adapting to climate change and the future of energy use. They are currently of an aspirational nature.

Table 9 Renewable technology projects for April 2011 to March 2015

Ref	Project	Lead	Cost		Annual Savings (yr 1)		Pay back (yrs)	Implementation Year
			Capital (C)	Operational (O)	Financial (Gross)	tCO <sub>2</sub>		
<b>Renewable Technologies</b>								
50	Solar Farm	Dave Cowley	£10,000,000 (C)		£375,000	2040.7	>10	<b>2012/2013</b>
51	Orford Community Sports Hub – PV roof array	Ian Lamb	£700,000 (C)		£13,860	75.4	>10	<b>2012/2013</b>
52	Schools Solar Project	Hilary Smith	£4,000,000 (C)		£145,728	793.2	>10	<b>2013/2014</b>
<b>Totals</b>			<b>£14,700,000</b>		<b>£534,588 (excluding feed in tariff)</b>	<b>2,909</b>	<b>N/A</b>	<b>N/A</b>

#### 4.4 Projected achievement towards target

To date we have identified a reduction of 33% of our 2009/10 carbon footprint highlighted in **Figure 9**. During the next 5 years we will seek to increase this reduction to at least 40% of our carbon footprint. Achieving our target will be reliant on funding being identified from a number of different internal and external sources. We will assess our progress annually and seek to identify further reductions and funding opportunities.




Figure 9 Planned progress towards our carbon reduction target



## 5 Carbon Management Plan Financing

To deliver our carbon savings and make long term steps towards sustainability for Warrington Borough Council we need to make substantial investment. The following section outlines our current position with financing and resources, the different sources of funding we will seek to finance projects and the criteria we will use to judge which projects are a priority.

### 5.1 Assumptions

To calculate the cost savings of our projects, a number of cost assumptions and price predications were made.

- Average electricity rate for stationary sources in 2010 10p / kWh
- Average gas rate for stationary sources in 2009 4p / kWh
- Average cost of a litre of petrol in 2009 is 98p
- Average cost of a litre of diesel in 2009 is 98p
- Energy costs rise by 1.7% annually over the 5 years of the plan
- Growth in CO<sub>2</sub> emissions from Council estate is 0.7% per annum
- 40% CO<sub>2</sub> reduction target is achieved by a 9% reduction annually from year 2 (having already identified 4% between April 2010 and March 2011).

### 5.2 Benefits / savings

Quantifiable Benefits:

Each project identified that saves carbon will bring financial savings in terms of reduced energy bills. These savings can be broken down annually as shown in **Table 10**.

	2009/2010	2010 / 2011	2011 / 2012	2012 / 2013	2013 / 2014	2014 / 2015
<b>Annual cost saving</b>	<b>£38,694</b>	<b>£137,686</b>	<b>£945,879</b>	<b>£1,484,885</b>	<b>£1,903,248</b>	<b>£2,044,169</b>
<b>Annual CO<sub>2</sub> saving</b>	<b>229.74</b>	<b>757.62</b>	<b>4827.76</b>	<b>7804.52</b>	<b>10369.09</b>	<b>11249.60</b>

*Table 10 Quantified Benefits and Savings of all projects*

Non-quantifiable benefits:

- Enhance the council's public image and green credentials
- Help the council adapt in the long term to changes in energy prices and pressures
- Leading the way for others in our community

### 5.3 Financial costs and sources of funding

To deliver our management plan we will need to make substantial investment. There are a number of invest to save projects in our plan that will see paybacks in less than 10 years and there are a number of projects that are based on longer term investment and sustainability. **Table 11** highlights the spread of this funding and the following paragraphs show where this funding will come from.

	2010/11	2011/12	2012/13	2013/14	2014/15	Ongoing
<b>Already spent</b>	<b>£884,639</b>					
<b>Funding for approved projects</b>		<b>£417,081</b>	<b>£323,081</b>	<b>£323,081</b>	<b>£323,081</b>	<b>£1,500,000<sup>(1)</sup></b>
<b>Funding needing to be sourced</b>		<b>£46,000</b>	<b>£1,225,498</b>	<b>£141,383</b>	<b>£26,383</b>	<b>£2,120,000</b>
<b>Renewable Technology funding to be sourced</b>		<b>£3,000,000</b>	<b>£7,000,000</b>	<b>£1,000,000</b>	<b>£1,000,000</b>	<b>£3,000,000<sup>(2)</sup></b>

Table 11 Financial costs of projects in plan

Notes
Assumption are prices correct at 2010/11 and do not include inflation
1. £250k per annum for a further 6 years
2. £1m per annum for a further 3 years

### Existing funding

We have had success with securing a range of funding including Salix Loans and Salix recycled fund monies to implement a number of these projects as outlined in section 4.1.

The Salix finance recycled funding loan means we will have an ongoing source of funding available for future smaller scale projects using the reinvestment of energy savings generated by the current funded energy saving projects. **Figure 10** demonstrates the Salix Recycling Fund process. Appendix A presents a worked example to illustrate the fund recycling process.

We have had success with securing some funding to implement a number of these projects, which has been outlined in Section 4.1. The Salix Finance recycled funding loan means we will have funding going back into a 'pot' to be reinvested as soon as the savings from projects are realised (see **Figure 11**).




Figure 10 The Salix recycling fund process




Figure 11 Salix recycled fund financing

### Warrington Borough Council Capital Programme

The council’s 10 year investment plan includes an annual notional capital budget of £250k for carbon reduction projects. Projects will be considered on an invest to save basis. WBC review the capital budget on a 6 monthly basis and if the opportunity arises there maybe more capital funding available.

We will be developing criteria to prioritise projects for funding, aiming to implement those with shorter payback periods sooner.

A key area for investment is in schools. We will be encouraging schools to identify potential projects for Salix investment. In addition we will be encouraging schools to seize any opportunities that may arise in their budgets to invest in energy reduction projects.

Operational costs for engagement programmes will be covered through team’s supplies and services budgets where they are of low monetary value.

### Funding to be sourced

For the reminder of our projects we will need to identify when funding streams become available and put in applications to help find the additional funding required. The climate change team will be able to assist teams who are looking to implement carbon reduction projects with their funding applications.

Prudential Borrowing is a source of funding that will need to be considered for large scale investment like the renewable projects. Salix loans requires a quick payback period therefore beneficial projects with longer paybacks and benefits can be considered, rather than limiting investigation to only short term projects. There may also be opportunities to identify Green Investment Bank funding in the future.

### Future funding

When further projects are identified to ensure we achieve our 40% reduction target, we will seek to identify funding either through current budgets or through new sources of funding that become available.

## 6 Actions to Embed Carbon Management in the Organisation

A key element of the Carbon Trust Programme is the management of change to embed carbon reduction into all the different parts of an organisation. If we are to be successful in achieving our carbon reduction targets, we will need everyone in the authority to work together towards this common goal. The Carbon Trust use a 'carbon management matrix' to illustrate the movement of an organisation between standard and best practice in carbon management (the matrix is reproduced in full in Appendix B). The matrix is designed to help organisations to embed carbon management across their organisation in 8 key areas:

- Corporate Strategy
- Programme Management
- Responsibility
- Data Management
- Communication and Training
- Finance and Investment
- Policy Alignment
- Engagement of schools

To embed carbon management across Warrington Borough Council we have sought to identify high level representatives to champion the key areas. Each of these representatives has pledged their support in achieving our carbon reduction objectives. We will monitor our progress in embedding carbon management within the organisation through our regular programme board, which is described in section 7.

The remainder of this section describes where we are in terms of carbon management, where we want to be, who is championing each activity and how we aim to get there. **Figure 12** shows where we were when we started the programme and where we aim to be. This will be monitored alongside the yearly reporting of our carbon footprint. A quarterly report will also be provided to the Climate Change board on the progress of the actions.




Figure 12 Carbon Management Matrix scores at the start of the plan and our targets for end score

## 6.1 Corporate Strategy – embedding CO<sub>2</sub> saving across Warrington Borough Council

Target	Level 5 by April 2013
Now	Level 3
Owner	Diana Terris, Chief Executive

We currently have a climate change strategy that has been signed off by the council. We have targets for CO<sub>2</sub> reduction clearly stated in our corporate plan and sustainable communities strategy.

To achieve the Level 5 target, the executive board will agree the adoption of the high level targets embodied in this plan, and will ensure that these are distributed across all directorates. We will seek to refresh our climate change strategy in 2011 and incorporate action plans that are reviewed annually.

Each director will be required to ensure that carbon management is included in their directorate business plan. In turn, each service manager will ensure that their service plans contribute to and support the carbon targets by inclusion of actions and responsibilities applicable to their service area.

Actions are required from:

- Executive Board
- Directors
- Service Managers

CORPORATE STRATEGY	
5	Top level target allocated across organisation CO <sub>2</sub> reduction targets in Directorate Business Plans Action plans in place to embed strategy. Progress routinely reviewed
4	CO <sub>2</sub> reduction commitment in Corporate Strategy Top level targets set for CO <sub>2</sub> reduction Climate Change Strategy reviewed annually
3	Vision for CO <sub>2</sub> reduction clearly stated and published Climate Change Strategy endorsed by Cabinet and publicised with staff
2	Draft Climate Change Policy Climate Change references in other strategies
1	No policy No Climate Change reference

## 6.2 Programme Management – bringing it all together effectively

Target	Level 5 by April 2013
Now	Level 3
Owner	Anton Fields, Programme Manager, <i>Transforming Warrington</i>

Section 7 of this document outlines the core teams that we have working on carbon reduction.

The primary group tasked with management of this programme is the climate change board. The board is overseen and reports into the transformation board, which includes representation from all three political parties and Warrington Borough Council's chief executive.

PROGRAMME MANAGEMENT	
5	Cabinet / SMT review progress against targets on quarterly basis Regular diagnostic reports provided to Directorates Progress against target published externally
4	CO <sub>2</sub> reduction commitment Sponsor reviews progress and removes blockages through regular Programme Boards Progress against targets routinely reported to Senior Mgt Team
3	Core team regularly review CM progress: o actions o profile & targets o new opportunities
2	Ad hoc reviews of CM actions progress
1	No CM monitoring

The transformation board reports in turn to the executive board, ensuring that the performance of the climate change programme will be safeguarded at the highest level.

The climate change team will provide reports every six weeks of performance against programme objectives to Transforming Warrington, which will enable oversight of all activities and progress to be made by the transformation board.

It is proposed to adopt the 'Managing Successful Programmes' (MSP) approach to the climate change programme to improve project management and accountability.

In addition, an annual review of progress against the carbon management plan will be made to cabinet in May each year in line with our carbon footprint for the previous financial year.

Actions are required from:

- Climate Change Board
- Transformation Board

### 6.3 Responsibility – being clear that saving CO<sub>2</sub> is everyone's job

Target	Level 5 by April 2014
Now	Level 4 (partial)
Owner	Diana Terris, Chief Executive

There are currently over 100 green champions across Warrington Borough Council. We have 2 full time officers working on carbon reduction and a number of key individuals in other directorates of the council that sit on the climate change implementation group.

To achieve level 5, responsibility for integrating carbon management will be divided across the council. Section 6.1 describes the process that we will follow to embed responsibility from senior management team down to each head of service, and ultimately into the day to day activities of each person through their service plans.

Actions to provide a centralised advisory and information service will be co-ordinated by the climate change Manager and communications, through well maintained information portals.

Actions are required from:

- Climate change board
- Climate change manager
- Climate change officer
- Communications team

RESPONSIBILITY	
5	CM integrated in responsibilities of senior managers CM part of all contracts / Ts & Cs Central CO <sub>2</sub> reduction advice available Green Champions leading local action groups
4	CO <sub>2</sub> reduction commitment CM integrated in to responsibilities of department heads Cabinet / SMT regularly updated Staff engaged through Green Champion network
3	An individual provides full time focus for CO <sub>2</sub> reduction Key individuals have accountability for carbon reduction Senior Sponsor actively engaged
2	CO <sub>2</sub> reduction a part-time responsibility of a few department champions
1	No recognised CO <sub>2</sub> reduction responsibility

### 6.4 Data Management – measuring the difference, measuring the benefit

DATA MANAGEMENT	
5	Regular collation of CO <sub>2</sub> emissions for all sources Data externally verified Monitoring & Targeting in place for: o buildings o street lighting o transport/travel
4	Annual collation of CO <sub>2</sub> emissions for: o buildings o street lighting o transport/travel Data internally reviewed
3	Collation of CO <sub>2</sub> emissions for limited scope i.e. buildings only
2	No CO <sub>2</sub> emissions data compiled Energy data compiled on a regular basis
1	No CO <sub>2</sub> emissions data compiled

Target	Level 5 by April 2012
Now	Level 4
Owner	Andy Farrall, Executive Director Environment & Regeneration

Data monitoring is already at a high standard, with collation on an annual basis of data and associated CO<sub>2</sub> emissions from buildings, street lighting, transport, water and waste.

Annual data collation will occur after March each year and reported to the Climate Change Board, chaired by Andy Farrall and then upwards to senior management teams.

Targeting systems are being set in place for all buildings and for specific items such as business travel to improve our data. It is our intention to investigate and introduce external data verification within this programme plan.

Actions are required from:

- Department heads (collection of appropriate data)
- Climate change officer (collation and reporting)
- Energy officer

### 6.5 Communication and Training – ensuring everyone is aware

Target	Level 5 by April 2014
Now	Level 2
Owner	Rachel Robins Director of People & Improvement

The communication and training currently at the council has been based around staff time. A presentation about the programme is given to new staff on the welcome to Warrington course and there is optional energy awareness training about home energy use for any front line staff.

Over the next 5 years we will introduce regular awareness campaigns and ensure that communication is a high priority. It will be scheduled into the yearly programme plan of the climate change team.

Regular press stories will be issued to communicate successes to the wider community.

There is a yearly staff survey into which we will insert questions to test staff awareness on the carbon reduction programme.

The Green team will be extended with training formalised and they will be asked to disseminate this back to their teams.

COMMUNICATION & TRAINING	
5	All staff given formalised CO <sub>2</sub> : o induction and training o communications Joint CM communications with key partners Staff awareness tested through surveys
4	All staff given CO <sub>2</sub> reduction: o induction o communications o CM matters communicated to external community
3	Environmental / energy group(s) given ad hoc: o training o communications
2	Regular awareness campaigns Staff given CM information on ad-hoc basis
1	No communication or training reference

The people and improvement services have their own action plan to help them achieve this goal.

Action required from

- Climate change team
- Communications team

People and Improvement Carbon Management Action Plan		
Owner – Rachel Robins		
Action	Target / Measure	Timescale
Ensure that staff engagement panel is consulted about any climate change awareness campaigns and decisions that will affect staff	Feedback from staff recorded and evaluated	Ongoing
Consult staff through employee survey	Awareness of environmental initiatives increase	Annually
Incorporate energy efficiency into existing and new staff training programmes where appropriate e.g. Premises managers	As stated	December 2011
Work to raise awareness and ownership of carbon emissions through leadership programme and future leaders programme	Information on programmes	Ongoing
Employee Recognition Scheme to include recognition for delivering carbon reduction or identifying opportunities	As stated	Ongoing
Warrington Rewards, ensure offers that can reduce staff's personal carbon footprints are advertised	As stated	Ongoing
Review directorate's own policies to ensure climate change is considered	As stated	December 2011



## 6.6 Finance and Investment – the money to match the commitment

Target	Level 5 by April 2015
Now	Level 2
Owner	Lynton Green Chief Finance Officer

Over the past few years there has been ad hoc financing for CO<sub>2</sub> reduction projects and match funding for the Salix invest to save fund.

Due to the current financial climate and uncertainty we are aiming to be at level 5 by 2015, in a position where each year we will be able to have finance committed for the next year for carbon reduction projects. We aspire to achieve level 5 within the programme plan; but since this is to some extent dependent on the national financial position, it will be reviewed in future years.

Since starting this programme it has been agreed that climate change invest to save project will receive £250k per year funding in the 10 year capital investment programme.

Action required from:

- Chief finance officer
- Climate Change Manager

FINANCE & INVESTMENT	
5	Finance committed for 2+yrs of Programme External funding being routinely obtained Ring-fenced fund for carbon reduction initiatives
4	Co-ordinated financing for projects via Programme Board Funding principles and processes agreed Finances committed 1year ahead Some external finance
3	A view of the cost of CO <sub>2</sub> reduction is developing, but finance remains ad-hoc Some centralised resource allocated Finance representation on CM Team
2	Ad hoc financing for CO <sub>2</sub> reduction projects
1	No specific funding for CO <sub>2</sub> reduction projects

## 6.7 Policy Alignment – saving CO<sub>2</sub> across our operations

Target	Level 5 by April 2015
Now	Level 2
Owner	Katherine Fairclough Assistant Chief Executive

There are only a few policies within the council that directly consider CO<sub>2</sub>; the local transport plan, the sustainable communities' strategy and the climate change strategy are the main documents.

To get to level 5 and ensure that all key policies incorporate CO<sub>2</sub> considerations we need to look at the corporate reporting process and aim to include a focus that takes into account CO<sub>2</sub> and sustainability considerations, both positive and negative. This will ensure that when both new and current policies are created or reviewed that CO<sub>2</sub> becomes a consideration. It will also allow us to monitor when a programme could have a big impact on our footprint.

The climate change team will be able to advise people on how to incorporate this into their plans and the reporting process will flag up when this is not being considered.

POLICY ALIGNMENT	
5	CO <sub>2</sub> friendly operating procedure in place Central team provide advice and review, when requested Barriers to CO <sub>2</sub> reduction routinely considered and removed
4	Comprehensive review of policies complete Lower level policies reviewed locally Unpopular changes being considered
3	All high level and some mid level policies reviewed, irregularly Substantial changes made, showing CO <sub>2</sub> savings
2	Partial review of key, high level policies Some financial quick wins made
1	No alignment of policies for CO <sub>2</sub> reduction

Action from:

- Climate Change team
- Policy and Performance Teams

### 6.8 Engagement of Schools – working with Schools to reduce their carbon footprint

ENGAGEMENT OF SCHOOLS	
5	A 'whole school approach' including curriculum Mature programme of engagement in place CO2 saving in schools having a wider community impact
4	A clear emphasis on energy / CO <sub>2</sub> reduction in schools Council activities fully co-ordinated Broad set of education stakeholders engaged Funding in place
3	A person has responsibility for Schools CO <sub>2</sub> reduction Schools CO <sub>2</sub> reduction projects co-ordinated Ad-hoc funding
2	Ad-hoc schools projects to specifically reduce energy / CO <sub>2</sub>
1	No CO <sub>2</sub> / energy reduction policy for schools

Target	Level 5 by April 2015
Now	Level 2
Owner	Kath O'Dwyer Executive Director, Children and Young People's Services

Schools are a key area for the council as they comprise the largest portion of our footprint at 40%. The value at stake for this area is £3,378,064, as illustrated in **Figure 13**.

The climate change team currently provide support and advice to those schools on the eco-schools programme and carbon reduction projects have been financed through external funding.

Children and Young People's services have committed to delivering new schools which achieve BREEAM status Very Good or better. Since 2007 three new school buildings have been created which incorporate sustainable technologies for heating and lighting.

The introduction of the Carbon Trust Programme provided an opportunity for us to join-up our approach to

sustainability initiatives in all schools and the development of comprehensive individual school plans for 2011 and beyond.

An action plan will be produced during 2011 to ensure that both curriculum and energy consumption is addressed in schools, this program will be lead by Children and Young People's Services Access and Assets Manager Hilary Smith.

Actions from:

- Climate change team
- Services access and assets manager – children's services




Figure 13 Value at Stake for Schools

## 7 Programme Management of the CM Programme

To ensure that this 5 year management plan is delivered we need a team of people engaged at different levels and different directorates across our organisation. A cross cutting approach needs to be taken in order to fully embed carbon management across the organisation.

Successful programme governance can be summarised as:

- Having a strategic overview of our carbon reduction
- Aligning our organisational objectives to include carbon management
- Ensure key players are engaged and active




Figure 14 Organisational context of carbon management programme

### 7.1 The Programme Board – strategic ownership and oversight

The programme board will meet every two months and ensure any blockages are removed from progressing the carbon management plan and make key decisions.

The progress of the climate change implementation group will be reported to the board to ensure the carbon management plan continues to move forward. This will be done through a highlight report (Appendix C) produced by the climate change implementation group members and compiled by the climate change officer.

The programme board minutes will be produced by the climate change officer and distributed to the board and the climate change implementation group.

The board will decide when there is key information to be reported to the senior management team, and our organisational routes will be followed.

The Programme Board will comprise of:

- Chair:** Andy Farrall - Executive Director of Environment and Regeneration
- Cllr Mike Biggin – Executive member for climate change and public protection
- Lynton Green – Chief Finance Officer
- David Boyer – Assistant Director - Transportation, Engineering and Climate Change
- Rachel Waggett – Climate Change Manager
- Laura Stanley – Climate Change Officer




Figure 15 Organisational chart for carbon management programme

## 7.2 The Climate Change Implementation Group – delivering the projects

The climate change implementation group will meet every two months, two weeks prior to the board meeting to enable the highlight report (Appendix C) to be produced for the board which identifies any progress made.

The climate change implementation group are responsible for delivering carbon reduction projects in their own areas. The group will report up to the climate change board through the climate change manager. The group membership will be reviewed regularly.

The climate change implementation group currently consists of people who cover areas that affect both our internal emissions and our borough’s emissions:

- Chair:** David Boyer - Assistant Director - Transportation, Engineering and Climate Change

- Rachel Waggett - Climate Change Manager
- Laura Stanley - Climate Change Officer
- Elwyn Rowlands - Architect & Building Maintenance Unit Manager
- Hilary Smith - Children and Young Peoples Services Access and Assets Manager
- Stewart Brown - Chief Estate & Valuation Officer
- Stephen Hunter - Service Manager - Strategic Transportation and Passenger Transport
- Paul McHenry - Waste Strategy Development & Imp Manager
- David Smith - Fleet Services & Vehicle Maintenance Manager
- Stuart Sykes - Head Of Procurement
- Alasdair Elder - Customer Services Manager (ICT)
- Ben Logan - HR Information Analyst
- Kevin Usher – Planning Policy Officer
- Jane Critchley – Head of Neighbourhoods in Warrington
- Dave Cowley – Head of Housing Services
- Charlie Shannon – Warrington Borough Transport
- Ian Robinson – Golden Gates Housing

## 7.2 Succession planning for key roles

The carbon management plans implementation relies on the embedding of the program into the organisation and commitment from our team. **Table 12** below shows the succession planning for our organisation.

Role	Action to reduce risk
Project Sponsor	Ensure that councillor sponsor and senior management team are regularly communicated to about the success of the carbon management plan and have full understanding. A series of briefing notes are being produced that will tell the story of the carbon management programme over time. If the project sponsor leaves then the person who takes this post will hold the agenda as part of their role.
Project Lead	Ensure the programme board and implementation group own their aspects of the programme. Ensure deputy project lead is aware of any management decisions and project lead and deputy project lead communicate regularly about the project. As above this should eliminate any problems if the project lead was to leave.
Deputy Project Lead	The deputy project lead will produce a guidance note about where the components of the project are kept along with carbon trust guidance on how to use them. If this role was to be lost then those above or those replacing the post holder would be able to continue delivering the programme.

*Table 12 Succession planning for key roles in Warrington Borough Councils carbon management plan*

## 7.3 Ongoing stakeholder management

To ensure ongoing stakeholder management we have worked with our communications team to produce a communications plan. This is shown in **Table 13**, and will be reviewed at each

climate change implementation group meeting to ensure that the group are delivering communications for good pieces of work.

Action Point	Action	Lead	Timescale	Audience
<b>External communications</b>				
<b>Press release</b>	Climate Change Team report to comms	Comms account manager/press team	As required	All press
<b>WIRE magazine</b>	Send articles in time for quarterly deadlines	Comms account manager/press team	As required	All residents who receive WIRE magazine
<b>Website</b>	Regular page updates	Climate Change Team	Bi Annual	All residents with access to the website
<b>Relevant interest groups</b>	Climate change team to update Low Carbon Lymm, Friends of the Earth and any new groups	Climate Change Team	Annually or as required	Interest groups
<b>Stronger Together – Our Streets</b>	Dependent on area, write articles when appropriate	Comms account manager	As required	All residents in the Stronger Together area
<b>Facebook &amp; twitter</b>	Regular updates on facebook and twitter	E-communications officer	Regular	All residents with access to internet
<b>Internal communications</b>				
<b>Intranet</b>	Climate Change Team report to comms to get regular updates on front page	Communications	Regular	All staff
<b>Departmental Management Team briefings</b>	Climate Change Team report to Senior management meetings.	Senior managers	Ongoing	Departmental Managers
<b>Member briefing</b>	Information to be included within member briefing. Information to be sent to Angela Horrigan	Climate Change Team	Monthly	Members
<b>Your Voice</b>	Feature in Your Voice – update.	Internal comms	Monthly	All staff
<b>Customer contact centre</b>	Brief staff in case of calls to contact Warrington following launch	Climate Change Team		All contact centre staff

Table 13 The climate change communications plan

#### **7.4 Annual progress review**

With the abolishment of national indicators and at the time of writing there being no formal process for reporting our carbon emissions to government, there is no requirement for us report our emissions.

Climate change is part of the transforming Warrington programme and is high on the council's agenda. As a result we will ensure that every April our yearly emissions are compiled and by June made public and reported to senior boards. This will consist of our carbon footprint, comparisons of consumption in each reportable area, cost savings, justifications for any changes and any wider sustainability achievement e.g. reductions in use of resources.

There are a number of internal performance indicators for climate change that means we will be regularly reporting the actions we are undertaking to reduce our emissions on a quarterly basis to members and senior managers. This can be used as an informal monitoring tool to ensure we reach yearly targets.

## APPENDIX A: Value at Stake Scenarios

Table 1: Description of scenario justifications

Scenario	Factor	Description	Rationale	Source
<b>Consumption</b>				
Low	0%	Annual change in energy and fuel demand as a result of new equipment, change in size of service etc.	No increase in consumption	Internal scenario
Central	0.7%		Consumption growth in line with nationally published figure in EP68.	EP68 publication by DTI (now BERR)
High	1.4%		Consumption growth at double the rate of nationally published figure in EP68.	Internal scenario
<b>Price</b>				
Low	-4.5%	Annual change in energy and fuel unit costs.	Reduction in unit costs in line with DECC 'low' scenario for electricity for 'services', averaged for 2009 -2014.	DECC energy price projects
Central	1.7%		Reduction in unit costs in line with DECC 'central' scenario for electricity for 'services', averaged for 2009 - 2014.	DECC energy price projects
High	4.2%		Reduction in unit costs in line with DECC 'high' scenario for electricity for 'services', averaged for 2009 - 2014.	DECC energy price projects

Table 14: Value at stake scenarios (figures are cumulative value at stake over 5 years)

		Price		
		Low	Central	High
Consumption	Low	£8,956,814	£9,356,025	£9,539,441
	Central	£9,697,991	£10,130,948	£10,329,906
	High	£10,453,137	£10,920,572	£11,135,413

The highlighted box indicates the scenario used in the carbon management plan.



**Salix Recycle Fund – worked example of project investment using this fund.**

<b>Project: Variable Speed Drive - Great Sankey Leisure Centre</b>					
<b>£12,000 project with 5 year payback</b>					
		<b>Project Cost</b>			
		<b>£12,000</b>	Loan	Cumulative	
		↑	Repayments	Repayments	
			(see notes)		
<b>WBC</b>	→	<b>Ring Fenced Fund</b> <b>£500k</b>	←	£2,400	£2,400
<b>Funding</b>			←	£2,400	£4,800
			←	£2,400	£7,200
<b>Salix</b>	→		←	£2,400	£9,600
<b>Funding</b>			←	£2,400	<b>£12,000</b>
			Loan repayment 5 years		
<b>Notes:</b>					
Revenue Savings calculated @ £3,200 per annum					
75% of revenue savings used to pay back into the fund @ £2,400					

## Appendix B: Carbon Management Matrix – Embedding

Now	3	3	4	4
In 5 yrs	5	5	5	5
Challenge				
	CORPORATE STRATEGY	PROGRAMME MANAGEMENT	RESPONSIBILITY	DATA MANAGEMENT
<b>Mature</b>  5	<ul style="list-style-type: none"> <li>Top level target allocated across organisation</li> <li>CO<sub>2</sub> reduction targets in Directorate Business Plans</li> <li>Action plans in place to embed strategy. Progress routinely reviewed</li> </ul>	<ul style="list-style-type: none"> <li>Cabinet / SMT review progress against targets on quarterly basis</li> <li>Regular diagnostic reports provided to Directorates</li> <li>Progress against target published externally</li> </ul>	<ul style="list-style-type: none"> <li>CM integrated in responsibilities of senior managers</li> <li>CM part of all contracts / Ts &amp; Cs</li> <li>Central CO<sub>2</sub> reduction advice available</li> <li>Green Champions leading local action groups</li> </ul>	<ul style="list-style-type: none"> <li>Regular collation of CO<sub>2</sub> emissions for all sources</li> <li>Data externally verified</li> <li>Monitoring &amp; Targeting in place for:                             <ul style="list-style-type: none"> <li>o buildings</li> <li>o street lighting</li> <li>o transport/travel</li> </ul> </li> </ul>
4	<ul style="list-style-type: none"> <li>CO<sub>2</sub> reduction commitment in Corporate Strategy</li> <li>Top level targets set for CO<sub>2</sub> reduction</li> <li>Climate Change Strategy reviewed annually</li> </ul>	<ul style="list-style-type: none"> <li>Sponsor reviews progress and removes blockages through regular Programme Boards</li> <li>Progress against targets routinely reported to Senior Mgt Team</li> </ul>	<ul style="list-style-type: none"> <li>CM integrated in to responsibilities of department heads</li> <li>Cabinet / SMT regularly updated</li> <li>Staff engaged through Green Champion network</li> </ul>	<ul style="list-style-type: none"> <li>Annual collation of CO<sub>2</sub> emissions for:                             <ul style="list-style-type: none"> <li>o buildings</li> <li>o street lighting</li> <li>o transport/travel</li> </ul> </li> <li>Data internally reviewed</li> </ul>
3	<ul style="list-style-type: none"> <li>Vision for CO<sub>2</sub> reduction clearly stated and published</li> <li>Climate Change Strategy endorsed by Cabinet and publicised with staff</li> </ul>	<ul style="list-style-type: none"> <li>Core team regularly review CM progress:                             <ul style="list-style-type: none"> <li>o actions</li> <li>o profile &amp; targets</li> <li>o new opportunities</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>An individual provides full time focus for CO<sub>2</sub> reduction</li> <li>Key individuals have accountability for carbon reduction</li> <li>Senior Sponsor actively engaged</li> </ul>	<ul style="list-style-type: none"> <li>Collation of CO<sub>2</sub> emissions for limited scope i.e. buildings only</li> </ul>
2	<ul style="list-style-type: none"> <li>Draft Climate Change Policy</li> <li>Climate Change references in other strategies</li> </ul>	<ul style="list-style-type: none"> <li>Ad hoc reviews of CM actions progress</li> </ul>	<ul style="list-style-type: none"> <li>CO<sub>2</sub> reduction a part-time responsibility of a few department champions</li> </ul>	<ul style="list-style-type: none"> <li>No CO<sub>2</sub> emissions data compiled</li> <li>Energy data compiled on a regular basis</li> </ul>
1 <b>Start</b>	<ul style="list-style-type: none"> <li>No policy</li> <li>No Climate Change reference</li> </ul>	<ul style="list-style-type: none"> <li>No CM monitoring</li> </ul>	<ul style="list-style-type: none"> <li>No recognised CO<sub>2</sub> reduction responsibility</li> </ul>	<ul style="list-style-type: none"> <li>No CO<sub>2</sub> emissions data compiled</li> <li>Estimated billing</li> </ul>

Carbon Management Plan

Now	2	2	2	2
In 5 yrs	5	4	5	5
Challenge		x	x	
	COMMUNICATION & TRAINING	FINANCE & INVESTMENT	POLICY ALIGNMENT *	ENGAGEMENT OF SCHOOLS
<b>Mature</b>  5	<ul style="list-style-type: none"> <li>All staff given formalised CO<sub>2</sub>:                             <ul style="list-style-type: none"> <li>o induction and training</li> <li>o communications</li> </ul> </li> <li>Joint CM communications with key partners</li> <li>Staff awareness tested through surveys</li> </ul>	<ul style="list-style-type: none"> <li>Finance committed for 2+yrs of Programme</li> <li>External funding being routinely obtained</li> <li>Ring-fenced fund for carbon reduction initiatives</li> </ul>	<ul style="list-style-type: none"> <li>CO<sub>2</sub> friendly operating procedure in place</li> <li>Central team provide advice and review, when requested</li> <li>Barriers to CO<sub>2</sub> reduction routinely considered and removed</li> </ul>	<ul style="list-style-type: none"> <li>A 'whole school approach' including curriculum</li> <li>Mature programme of engagement in place</li> <li>CO<sub>2</sub> saving in schools having a wider community impact</li> </ul>
4	<ul style="list-style-type: none"> <li>All staff given CO<sub>2</sub> reduction:                             <ul style="list-style-type: none"> <li>o induction</li> <li>o communications</li> <li>o CM matters</li> </ul> </li> <li>~ communicated to external community</li> </ul>	<ul style="list-style-type: none"> <li>Co-ordinated financing for CO<sub>2</sub> reduction projects via Programme Board</li> <li>Funding principles and processes agreed</li> <li>Finances committed 1 year ahead</li> <li>Some external financing</li> </ul>	<ul style="list-style-type: none"> <li>Comprehensive review of policies complete</li> <li>Lower level policies reviewed locally</li> <li>Unpopular changes being considered</li> </ul>	<ul style="list-style-type: none"> <li>A clear emphasis on energy / CO<sub>2</sub> reduction in schools</li> <li>Council activities fully co-ordinated</li> <li>Broad set of education stakeholders engaged</li> <li>Funding in place</li> </ul>
3	<ul style="list-style-type: none"> <li>Environmental / energy group(s) given ad hoc:                             <ul style="list-style-type: none"> <li>o training</li> <li>o communications</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>A view of the cost of CO<sub>2</sub> reduction is developing, but finance remains ad-hoc</li> <li>Some centralised resource allocated</li> <li>Finance representation on CM Team</li> </ul>	<ul style="list-style-type: none"> <li>All high level and some mid level policies reviewed, irregularly</li> <li>Substantial changes made, showing CO<sub>2</sub> savings</li> </ul>	<ul style="list-style-type: none"> <li>A person has responsibility for Schools CO<sub>2</sub> reduction</li> <li>Schools CO<sub>2</sub> reduction projects co-ordinated</li> <li>Ad-hoc funding</li> </ul>
2	<ul style="list-style-type: none"> <li>Regular awareness campaigns</li> <li>Staff given CM information on ad-hoc basis</li> </ul>	<ul style="list-style-type: none"> <li>Ad hoc financing for CO<sub>2</sub> reduction projects</li> </ul>	<ul style="list-style-type: none"> <li>Partial review of key, high level policies</li> <li>Some financial quick wins made</li> </ul>	<ul style="list-style-type: none"> <li>Ad-hoc schools projects to specifically reduce energy / CO<sub>2</sub></li> </ul>
1 <b>Start</b>	<ul style="list-style-type: none"> <li>No communication or training</li> </ul>	<ul style="list-style-type: none"> <li>No specific funding for CO<sub>2</sub> reduction projects</li> </ul>	<ul style="list-style-type: none"> <li>No alignment of policies for CO<sub>2</sub> reduction</li> </ul>	<ul style="list-style-type: none"> <li>No CO<sub>2</sub> / energy reduction policy for schools</li> </ul>

## Appendix C: Highlight Report

<b>Programme Name:</b>	Climate Change			
<b>Prepared by:</b>	Climate Change Officer			
<b>Date:</b>				
<b>PID Version:</b>				
<b>1. Programme Summary</b>				
<b>Overall Status:</b>	<b>Green<sup>1</sup></b>	<b>Orange<sup>2</sup></b>	<b>Red<sup>3</sup></b>	<b>Reason for deviation / Board attention required</b>
<b>Asset management</b> - CRC - Salix - Estates energy (Stewart Brown, Elwyn Rowlands, Rachel Waggett)				
<b>Schools</b> (Hilary Smith)				
<b>Information technology</b> (Alasdair Elder)				
<b>Carbon management programmes</b> (Rachel Waggett) - 10:10 - Cheshire Groups - Carbon Trust LAMP - EST 1 to 1				
<b>Sustainable land use patterns</b> (Kevin Usher)				
<b>Travel and Transport</b> (Steve Hunter, Ben Logan)				
<b>Street lighting</b> (Dave Vassey)				
<b>Waste management</b> (Paul Mchenry)				
<b>Fleet and Buses</b> (David Smith, Charlie Shannon)				
<b>Engagement</b> (Jane Critchley, Rachel Waggett)				
<b>Domestic carbon</b> (Dave Cowley)				
<b>Sustainable procurement</b> (Stuart Sykes)				
<b>Adaptation</b> (Rachel Waggett)				



working with



Carbon Management Plan

<p><sup>1</sup> Programme is within tolerance.</p> <p><sup>2</sup> Programme is likely to or has deviated slightly from the plan or tolerance level.</p> <p><sup>3</sup> Programme is likely to or has significantly behind plan or tolerance level.</p>
<p><b>Programme Manager’s Comments:</b></p>
<p><b>Carbon Savings to Date:</b></p> <p><b>Other Recordable figures:</b></p>
<p><b>2010 / 2011 Carbon Target</b></p>

Asset Management (Elwyn Rowlands, Stewart Brown, Rachel Waggett)	
<b>Accomplishments during this Reporting Period</b>	
<ul style="list-style-type: none"> <li>•</li> </ul>	
<b>Plans during the next Reporting Period :</b>	
<ul style="list-style-type: none"> <li>•</li> </ul>	
<b>Items Requiring Management or Board Attention:</b>	
<ul style="list-style-type: none"> <li>•</li> </ul>	
Recordable Carbon Savings or Engagement Figures	

This continues for:

- Information Technology
- Carbon Management Programmes
- Sustainable land use patterns
- Sustainable mobility
- Street lighting
- Waste Management
- Travel and Transport
- Engagement
- Domestic Carbon
- Sustainable Procurement
- Adaptation

## Appendix D: Definition of Projects

The project definition sheets over the remaining pages provide supplementary information and extra detail to section 4. They outline projects in more detail and the assumptions used to quantify them.

### Building and Engagement Programmes

<b>Project:</b>	<b>St Margaret's Primary Rationalisation</b>
<b>Reference:</b>	16
<b>Owner (person)</b>	Hilary Smith
<b>Department</b>	Children and Young People
<b>Description</b>	<p>The existing St Margaret's Primary School Junior building will be extended to consolidate the infant and junior provision on the same site. This will approximately double the size of the existing junior school. The infant school will then be closed.</p> <p>The opportunity to improve carbon across the school has been taken, with the new extension meeting very high standards of energy efficiency. The retained element of the Junior school will also benefit from a new heating system and new lighting systems and controls.</p>
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings: £3,328 per year</li> <li>Payback period: Immediate</li> <li>CO<sub>2</sub> Emissions reduction: 80 tonnes per year</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>The energy efficiency measures have been included in this project without increasing the overall budget.</li> <li>Operational costs are likely to reduce rather than otherwise, therefore zero.</li> <li>Source of funding: internal.</li> <li>Decision to go ahead has been made.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>Additional resource : advice from climate change team and planning team, delivered within current resources.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Design team and client need to make sure that energy efficiency improvements remain in the project through implementation.</li> <li>Low risk as proven measures.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Electricity and gas meter readings/bills show a reduction in energy use against previous consumption.</li> <li>Annually at financial year end.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>Milestones / key dates <ul style="list-style-type: none"> <li>start date: July 2011</li> <li>completion date (when it will deliver savings): April 2012</li> </ul> </li> </ul>
<b>Notes</b>	See attached calculation sheet. Projections of future energy use provided by Design Team.

<b>Project:</b>	<b>Rationalisation of Bruche Primary</b>																																					
<b>Reference:</b>	17																																					
<b>Owner (person)</b>	Hilary Smith																																					
<b>Department</b>	Children and Young People																																					
<b>Description</b>	Demand for pupil places at Bruche has reduced from requirement for 420 in the past to 210 currently and foreseeable future. The school was accommodated across 2 separate infant and junior buildings but is now being rationalised into one building only. There is capital investment in the junior building currently in order to remodel and make it suitable for a 210 place primary school The infant building will be taken out of use and services disconnected..																																					
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings: £6,952</li> <li>Payback period: 0 years</li> <li>CO<sub>2</sub> Emissions reduction: 44.7 tonnes</li> </ul>																																					
<b>Funding</b>	Approximately £500K to modernise and remodel the junior building.																																					
<b>Resources</b>	Central Government Grant: Primary Capital Programme																																					
<b>Ensuring Success</b>	Infant building to be taken out of use to ensure that assets are fully utilised and resources used efficiently and effectively.																																					
<b>Measuring Success</b>	Engagement with school community to ensure that the new primary school building is operated and maintained effectively and efficiently.																																					
<b>Timing</b>	Capital Project Completion: March 2011 Pupils and transfer transfer to new facility: April 2011 Benefits start to be realised with effect from April 2011																																					
<b>Notes</b>	<table border="1"> <tr> <td colspan="3"><b>Before Rationalisation</b></td> </tr> <tr> <td colspan="3"><b>Energy for 2009/2010</b></td> </tr> <tr> <td>Electricity</td> <td>109,139</td> <td rowspan="2">Floor area 2476</td> </tr> <tr> <td>Gas</td> <td>301,833</td> </tr> <tr> <td colspan="3"><b>Energy per metre squared based on the above</b></td> </tr> <tr> <td>Electricity</td> <td>44.07875606</td> <td rowspan="2"></td> </tr> <tr> <td>Gas</td> <td>121.9034733</td> </tr> <tr> <td colspan="3"><b>After Rationalisation (based on energy per square metre)</b></td> </tr> <tr> <td>Electricity</td> <td>66647.07916</td> <td rowspan="2">Floor area 1512</td> </tr> <tr> <td>Gas</td> <td>184318.0517</td> </tr> <tr> <td colspan="3"><b>Energy Saving</b></td> </tr> <tr> <td>Electricity</td> <td>42,492</td> <td rowspan="2"></td> </tr> <tr> <td>Gas</td> <td>117,515</td> </tr> </table>		<b>Before Rationalisation</b>			<b>Energy for 2009/2010</b>			Electricity	109,139	Floor area 2476	Gas	301,833	<b>Energy per metre squared based on the above</b>			Electricity	44.07875606		Gas	121.9034733	<b>After Rationalisation (based on energy per square metre)</b>			Electricity	66647.07916	Floor area 1512	Gas	184318.0517	<b>Energy Saving</b>			Electricity	42,492		Gas	117,515	Figures used to calculate carbon and cost savings
<b>Before Rationalisation</b>																																						
<b>Energy for 2009/2010</b>																																						
Electricity	109,139	Floor area 2476																																				
Gas	301,833																																					
<b>Energy per metre squared based on the above</b>																																						
Electricity	44.07875606																																					
Gas	121.9034733																																					
<b>After Rationalisation (based on energy per square metre)</b>																																						
Electricity	66647.07916	Floor area 1512																																				
Gas	184318.0517																																					
<b>Energy Saving</b>																																						
Electricity	42,492																																					
Gas	117,515																																					

<b>Project:</b>	<b>Rationalisation of Horizons (Pupil Referral Unit)</b>																									
<b>Reference:</b>	18																									
<b>Owner</b>	Hilary Smith																									
<b>Department</b>	Children and Young People																									
<b>Description</b>	<p>Horizons is a short break provision for children with emotional and behavioural difficulties. The provision is currently located across two sites. Neither site is fit for purpose, buildings are in poor condition and heating and lighting systems are inefficient. In addition management and teaching staff spend a significant amount of time travelling between the two sites in order to deliver services to all pupils enrolled.</p> <p>A former primary school, which is in reasonably good condition (significantly better than either of the 2 Horizon's sites) has become available following the close of the primary school in August 2010. The primary school building has sufficient capacity for all children and staff at Horizons to be accommodated under one roof. Consequently a project to remodel the primary school in order to make it fit for purpose for Horizons has been developed and will be implemented in June 2011 and completed at the end of 2011. Horizon staff and pupils will move into the facility in December 2011. In January 2012 the former Horizons buildings will be taken out of use.</p>																									
<b>Benefits</b>	<p>Reduced carbon footprint as a result of (i) no requirement for management and teaching staff to move between sites in order to provide services to Horizon pupils; and (ii) improved quality environment and more energy efficient building.</p> <ul style="list-style-type: none"> <li>• Financial savings: £39,702</li> <li>• Payback period: 0 years</li> <li>• CO<sub>2</sub> Emissions reduction: 266.3 tonnes</li> </ul>																									
<b>Funding</b>	£500,000																									
<b>Resources</b>	Central Government Capital Grant for Local Authorities.																									
<b>Ensuring Success</b>	Engagement with school community to ensure that the new facility is operated and maintained effectively and efficiently.																									
<b>Measuring Success</b>	Comparison of energy consumption for Horizons pre and post Implementation.																									
<b>Timing</b>	<p>Project implementation: June 2011      Project Completion: November 2011</p> <p>Move to new facility: December 2011</p> <p>Open on new site: effective from January 2012</p>																									
<b>Notes</b>	<p>Figures used to calculate carbon and cost savings</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 60%;">Horizons (Grappenhall Hall)</td> <td style="width: 20%; text-align: right;">256,277 Kwh</td> <td style="width: 20%;">Elec 09/10</td> </tr> <tr> <td></td> <td style="text-align: right;">1,024,657 Kwh</td> <td>Gas 09/10</td> </tr> <tr> <td>Horizons (Lousehers Lane)</td> <td style="text-align: right;">26,272 Kwh</td> <td>Elec 09/10</td> </tr> <tr> <td></td> <td></td> <td>Gas 09/10</td> </tr> <tr> <td>New site (former Longbarn Primary School)</td> <td style="text-align: right;">82,118 Kwh</td> <td>Elec 09/10</td> </tr> <tr> <td></td> <td style="text-align: right;">169,925 Kwh</td> <td>Gas 09/10</td> </tr> <tr> <td style="text-align: right;">200,431 Kwh</td> <td><b>Elec Difference</b></td> <td></td> </tr> <tr> <td style="text-align: right;">854,732 Kwh</td> <td><b>Gas Difference</b></td> <td></td> </tr> </table>		Horizons (Grappenhall Hall)	256,277 Kwh	Elec 09/10		1,024,657 Kwh	Gas 09/10	Horizons (Lousehers Lane)	26,272 Kwh	Elec 09/10			Gas 09/10	New site (former Longbarn Primary School)	82,118 Kwh	Elec 09/10		169,925 Kwh	Gas 09/10	200,431 Kwh	<b>Elec Difference</b>		854,732 Kwh	<b>Gas Difference</b>	
Horizons (Grappenhall Hall)	256,277 Kwh	Elec 09/10																								
	1,024,657 Kwh	Gas 09/10																								
Horizons (Lousehers Lane)	26,272 Kwh	Elec 09/10																								
		Gas 09/10																								
New site (former Longbarn Primary School)	82,118 Kwh	Elec 09/10																								
	169,925 Kwh	Gas 09/10																								
200,431 Kwh	<b>Elec Difference</b>																									
854,732 Kwh	<b>Gas Difference</b>																									



<b>Project:</b>	<b>New Build Chapelford Primary School</b>											
<b>Reference:</b>	19											
<b>Owner (person)</b>	Hilary Smith											
<b>Department</b>	Children & Young People's Services											
<b>Description</b>	<p>Design and Construction of a new build primary school at Chapelford to serve new community and to replace the existing Sycamore Lane Community Primary School.</p> <p>The facility will replace existing facilities at Sycamore Lane when it is completed, currently planned for July 2012.</p>											
<b>Benefits</b>	<ul style="list-style-type: none"> <li>CO<sub>2</sub> Emissions reduction: 62.86 tonnes per year (see notes)</li> </ul>											
<b>Funding</b>	<ul style="list-style-type: none"> <li>Within current budgets</li> </ul>											
<b>Resources</b>	<ul style="list-style-type: none"> <li>Within current resources</li> </ul>											
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Carbon targets in Employer's Requirements and other design requirements must be maintained throughout design and tender phase.</li> <li>Attention must be paid to maintaining energy efficiency of design during detailed design and construction, to ensure that achievements are maintained.</li> </ul>											
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Measuring energy performance in early years of occupation.</li> <li>Year one, two and three following occupation.</li> </ul>											
<b>Timing</b>	<ul style="list-style-type: none"> <li>Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>start date: Start on site June 2011</li> <li>completion date (when it will deliver savings): September 2012</li> </ul> </li> </ul>											
<b>Notes</b>	<p>The carbon benefits from this project involve the replacement of Sycamore Lane Community Primary with the new Chapelford Primary School.</p> <table border="1"> <tr> <td>Sycamore Lane CO<sub>2</sub> 07/08 elec (latest completed data) 09/10 gas</td> <td>100 tonnes</td> </tr> <tr> <td>Chapelford CO<sub>2</sub> regulated emissions prediction (based on design target of 15kgCO<sub>2</sub>/m<sup>2</sup>/year with floor area 1650m<sup>2</sup>).</td> <td>24.75 tonnes</td> </tr> <tr> <td>Chapelford CO<sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)</td> <td>12.38 tonnes</td> </tr> <tr> <td>Total predicted Chapelford CO<sub>2</sub> emissions</td> <td>37.13 tonnes</td> </tr> <tr> <td><b>CO<sub>2</sub> saving from project per year</b></td> <td><b>62.86 tonnes</b></td> </tr> </table>		Sycamore Lane CO <sub>2</sub> 07/08 elec (latest completed data) 09/10 gas	100 tonnes	Chapelford CO <sub>2</sub> regulated emissions prediction (based on design target of 15kgCO <sub>2</sub> /m <sup>2</sup> /year with floor area 1650m <sup>2</sup> ).	24.75 tonnes	Chapelford CO <sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)	12.38 tonnes	Total predicted Chapelford CO <sub>2</sub> emissions	37.13 tonnes	<b>CO<sub>2</sub> saving from project per year</b>	<b>62.86 tonnes</b>
Sycamore Lane CO <sub>2</sub> 07/08 elec (latest completed data) 09/10 gas	100 tonnes											
Chapelford CO <sub>2</sub> regulated emissions prediction (based on design target of 15kgCO <sub>2</sub> /m <sup>2</sup> /year with floor area 1650m <sup>2</sup> ).	24.75 tonnes											
Chapelford CO <sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)	12.38 tonnes											
Total predicted Chapelford CO <sub>2</sub> emissions	37.13 tonnes											
<b>CO<sub>2</sub> saving from project per year</b>	<b>62.86 tonnes</b>											

<b>Project:</b>	<b>New Build Great Sankey Primary School</b>											
<b>Reference:</b>	20											
<b>Owner (person)</b>	Hilary Smith											
<b>Department</b>	Children & Young People's Services											
<b>Description</b>	<p>Design and Construction of a new build primary school at Great Sankey to replace the existing Great Sankey Primary School on a new site.</p> <p>The new school will replace existing facilities when it is completed, currently planned for July 2012.</p>											
<b>Benefits</b>	<ul style="list-style-type: none"> <li>CO<sub>2</sub> Emissions reduction: 409.47 tonnes per year (see notes)</li> </ul>											
<b>Funding</b>	<ul style="list-style-type: none"> <li>Within current budgets</li> </ul>											
<b>Resources</b>	<ul style="list-style-type: none"> <li>Within current resources</li> </ul>											
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Carbon targets in Employer's Requirements and other design requirements must be maintained throughout design and tender phase.</li> <li>Attention must be paid to maintaining energy efficiency of design during detailed design and construction, to ensure that achievements are maintained.</li> </ul>											
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Measuring energy performance in early years of occupation.</li> <li>Year one, two and three following occupation.</li> </ul>											
<b>Timing</b>	<ul style="list-style-type: none"> <li>Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>start date: Start on site June 2011</li> <li>completion date (when it will deliver savings): September 2012</li> </ul> </li> </ul>											
<b>Notes</b>	<p>The carbon benefits from this project involve the replacement of the existing Great Sankey Primary School with a new school on an adjacent site.</p> <table border="1" data-bbox="475 1317 1342 1740"> <tr> <td>Great Sankey (existing) CO<sub>2</sub> 09/10 (latest completed data)</td> <td>452 tonnes</td> </tr> <tr> <td>Great Sankey (new build) CO<sub>2</sub> regulated emissions prediction (based on design target of 15kgCO<sub>2</sub>/m<sup>2</sup>/year with floor area 1890m<sup>2</sup>).</td> <td>28.35 tonnes</td> </tr> <tr> <td>Great Sankey (new build) CO<sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)</td> <td>14.18 tonnes</td> </tr> <tr> <td>Total predicted Great Sankey (new build) CO<sub>2</sub> emissions</td> <td>42.53 tonnes</td> </tr> <tr> <td><b>CO<sub>2</sub> saving from project per year</b></td> <td><b>409.47 tonnes</b></td> </tr> </table>		Great Sankey (existing) CO <sub>2</sub> 09/10 (latest completed data)	452 tonnes	Great Sankey (new build) CO <sub>2</sub> regulated emissions prediction (based on design target of 15kgCO <sub>2</sub> /m <sup>2</sup> /year with floor area 1890m <sup>2</sup> ).	28.35 tonnes	Great Sankey (new build) CO <sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)	14.18 tonnes	Total predicted Great Sankey (new build) CO <sub>2</sub> emissions	42.53 tonnes	<b>CO<sub>2</sub> saving from project per year</b>	<b>409.47 tonnes</b>
Great Sankey (existing) CO <sub>2</sub> 09/10 (latest completed data)	452 tonnes											
Great Sankey (new build) CO <sub>2</sub> regulated emissions prediction (based on design target of 15kgCO <sub>2</sub> /m <sup>2</sup> /year with floor area 1890m <sup>2</sup> ).	28.35 tonnes											
Great Sankey (new build) CO <sub>2</sub> unregulated emissions prediction (assume 50% of regulated predicted emissions)	14.18 tonnes											
Total predicted Great Sankey (new build) CO <sub>2</sub> emissions	42.53 tonnes											
<b>CO<sub>2</sub> saving from project per year</b>	<b>409.47 tonnes</b>											

<b>Project:</b>	<b>Schools Engagement Program</b>
<b>Reference:</b>	21
<b>Owner (person)</b>	Hilary Smith
<b>Department</b>	Children and young peoples services
<b>Description</b>	Starting with the Secondary schools this program aims to support schools develop a carbon reduction plan. We will support schools on soft measures such as progressing with eco-schools and also provide support and advice on energy management. The program commenced in December 2010 with the secondary schools after this we will commence a similar approach with primary and special schools.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings: £117,950</li> <li>CO<sub>2</sub> Emissions reduction: 674 tonnes (5% of schools energy)</li> <li>Increased recycling and better use of natural resources</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>The project will be run with a minimal/no budget.</li> <li>Any funding that is required will come from CYPS Access and Asset Services or the climate change team.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>Staff time from Access and Assets and climate change</li> <li>Staff time from schools business managers and teachers</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Key factors to success include: Buy in from schools Staff time to support schools</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Schools energy consumption will be monitored during the program and measured at the end of each financial year.</li> <li>Quick wins and no cost measures will be identified and implementation monitored across the year. An impact assessment will be completed in year 2.</li> </ul>
<b>Timing</b>	<p>Started on secondary schools: November 2010                  All schools engaged: March 2012                  Continual support after this time and the potential to develop a new program.</p>

**Project definition**

Reference	22
Title	Eco-rep in each team
Description	Expand the Green team to ensure there is an eco-rep in each service within the authority
Owner	Laura Stanley
Directorate / team	Climate Change
Director responsible	Andy Farrell
Date submitted	07 October 2010

**Carbon savings**

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Electricity (grid)	698,925	kWh/yr	698,925	382,081
Carbon source 2:					

Data quality Estimates

Quantification method Estimate given from carbon trusts deck of cards 5% saving of electricity energy (excluding streetlighting) from having active and engagement

**Financial**

Capital cost	
Annual operating cost	£500
Gross annual savings	£55,914
Net annual savings	£55,414
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	0.0

Funding source(s)

1. Climate supplies and services budget
2. Cheshire and Warrington Public Sector Carbon Management Group

**Risk assessment**

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Staff don't undertake roll fully	Medium	Ensure full engagement	Medium	Mointoring

**Project status and next steps**

Current Status of Project	Estimated costs
Enabling Actions to Change Status	Gain approval to extend the green team with a report for assistant directors

### Carbon savings

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Natural gas (kWh)	1,178,493	kWh/yr	1,178,493	216,796
Carbon source 2:					

Data quality Estimates

Quantification method Estimates from RAP tool

### Financial

Capital cost	£117,849
Annual operating cost	
Gross annual savings	£27,105
Net annual savings	£27,105

Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	4.3

### Risk assessment

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified
Finance: Operational expense	Medium			

### Project status and next steps

Overall status	Green
Current status of data	RAP tool estimate
Enabling actions to change status	Cost based on cost per kwh of sites this technology has been identified suitable for

Save this file to: [enter folder path here]

\* Note that this simple payback calculation only considers capital cost, maintenance cost, and revenues from abated energy use. Other cost factors may also be relevant (e.g. changing energy/fuel prices), and it is recommended that this calculation is che

**Project definition**

Reference	24
Title	Broomfields Leisure, Building Management System
Description	As above
Owner	Mark McGiveron
Directorate / team	Climate Change
Director responsible	Andy Farrell
Date submitted	20th January 2011

**Carbon savings**

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Natural gas (kWh)	129,000	kWh/yr	129,000	23,731
Carbon source 2:					

Data quality	Estimates
Quantification method	Research done for Salix Financing

**Financial**

Capital cost	£18,000
Annual operating cost	
Gross annual savings	£2,709
Net annual savings	£2,709
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	6.6

**Risk assessment**

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified

**Project status and next steps**

Overall status	Green
Current status of data	Estimated costs
Enabling actions to change status	Gain finance approval

<b>Project:</b>	<b>Council office Accommodation strategy</b>
<b>Reference:</b>	25
<b>Owner (person)</b>	Stewart Brown
<b>Department</b>	Environment & Regeneration, Estates & Valuation
<b>Description</b>	To review and define the Councils short and medium term office accommodation needs
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings by rationalising its office accommodation, reducing building numbers and increasing utilisation amounts to be defined as the review takes form. Current spend for buildings we are looking to rationalise for energy &amp; maintenance equate to nearly £300k over a 6 to 8 year period.</li> <li>If as rationalisation continues as currently planned, the electricity and gas for these buildings will be reduced, however electricity &amp; gas will still be consumed within in an alternative building. Savings should be made, reasonable to project a 20% reduction. This equates to 75 tonnes of CO<sub>2</sub>.</li> <li>A number of public buildings are considered for closure (subject to consultation) with services not moved elsewhere. Savings here will equate to 145 tonnes.</li> <li><b>Total CO<sub>2</sub> as of November 2010 – 220 tonnes</b></li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>Operational costs, e.g. annual maintenance or running costs will be distributed across any buildings staffs are moved into.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>This project will be delivered within current Estates staffing &amp; financial planning resources</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Key success factors, senior management and Executive board approval, accurate projections on staffing needs over short and medium term, being able to dispose of surplus properties at full commercial rates.</li> <li>Principal risks: inaccurate staffing projections, lack of senior management or executive member approval to proposals, not being able to sell buildings.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Space audit results on staff utilisation and space given over to document storage.</li> <li>Reduced building budgets reflecting disposals of existing offices</li> <li>Annual space audit will show phased improvements of utilisation and rationalisation of offices</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>start date: spring 2011</li> <li>completion date (when it will deliver savings): Ongoing</li> </ul> </li> </ul>
<b>Notes</b>	<ul style="list-style-type: none"> <li>Rationalisation will be an ongoing process to be reviewed annually in the current economic climate.</li> </ul>

<b>Project:</b>	<b>Energy Audits Program</b>
<b>Reference:</b>	26 - 32
<b>Owner (person)</b>	Mark McGiveron
<b>Department</b>	Environment and Regeneration
<b>Description</b>	The audit program is looking at 108 council owned buildings. All assessments will be completed by March 2012. The audits identify projects that are suitable for individual sites such as voltage optimisation and variable speed drives. Example is provided below.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings: £325,837</li> <li>Payback period: Various – Individual projects will have different payback periods. Majority of projects will payback in 5 years.</li> <li>CO<sub>2</sub> Emissions reduction: 1,923 tonnes</li> </ul>
<b>Funding</b>	<p>Total cost of project - £957,438</p> <p>Funding mainly will be through the climate change capital funding through council budgets.</p> <p>The current Salix invest to save pot can also be utilised.</p> <p>This means all projects should be delivered by March 2014</p>
<b>Resources</b>	This project will be delivered by the current resources available
<b>Ensuring Success</b>	<p>Need to make sure there is the budget is secured to deliver these projects</p> <p>Need to work with partners to ensure those who have measures undertaken are willing to pay back.</p>
<b>Measuring Success</b>	Energy will be monitored for buildings before and after projects are implemented
<b>Timing</b>	<ul style="list-style-type: none"> <li>Start date: 01/04/2011</li> <li>Projects to be delivered on an ongoing basis</li> <li>completion date (when it will deliver savings): 31/03/2014</li> </ul>
<b>Notes</b>	To quantify the projects that have been identified through the audit program, the figures for energy saved from the surveyors has been used

### Example of projects that come out of the energy audit program

Building	Project Type	Project	Project Budget Cost	Potential kWh Savings	Potential Cost Savings	Possible Payback
Lymm High	Heating	Cooling and Heating running at same time	200	14,000	294	0.68
Lymm High	Heating	Recommission TREND BEMS	7,000	142,000	2,982	2.35
Lymm High	Lighting	Replace Tungsten Lamps	500	4,361	362	1.38
Lymm High	pool	Replace Pool Heat Exchanger	5,000	75,000	1,575	3.17
Lymm High	pool	Reduce Filter Back wash	5,000	75,000	1,575	3.17
Lymm High	vsd	VSD to Pool Pumps	7,000	35,000	2,905	2.41
Lymm High	pool	Renew Pool Cover	18,000	250,000	5,250	3.43
Lymm High	Lighting	Replace spot light to LEDs	650	2,175	181	3.60
Lymm High	insulation	Block B roofing insulation	3,000	25,000	525	5.71
Lymm High	Lighting	Lighting Controls, Zones and PIR	10,000	30,895	2,564	3.90
Lymm High	Lighting	Replace Gym T12 Lighting to T5	850	1,951	162	5.25



<b>Project:</b>	<b>Audit of Libraries and Community Centres to Identify Projects</b>
<b>Reference:</b>	33
<b>Owner (person)</b>	Mark McGiveron
<b>Department</b>	Environment and Regeneration
<b>Description</b>	Commission / Deliver an audit of our libraries and community centres which will in turn identify projects that will deliver carbon savings.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £35,756</li> <li>• Payback period: Various – Individual projects will have different payback periods. Majority of projects will payback in 5 years.</li> <li>• CO<sub>2</sub> Emissions reduction: 221 tonnes</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost                             <ul style="list-style-type: none"> <li>- Audits £750 per audit based on 2010 prices</li> <li>- Projects £108,709</li> </ul> </li> <li>• Funding mainly will be capital funding through council capital budgets and the salix fund.</li> </ul> <p>The current Salix invest to save pot can also be utilised.</p>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• The organisation of this project can be delivered within current resources</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• To ensure success and minimise risk of this project it is vital that we secure funding for audits.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Audits delivered, projects implemented and delivering carbon savings</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ start date: April 2013</li> <li>○ completion date (when it will deliver savings): April 2014</li> </ul> </li> </ul> <p>A later start date for this project enables us to finish and implement the projects from the current audit programs.</p>
<b>Notes</b>	<p>Total Gas usage for Libraries and Community Centres – 2,270,279 Kwh</p> <p>Total Electricity usage for Libraries and Community Centres – 1,265,617 Kwh</p> <p>Assuming a 20% reduction as the current audit program is finding approximately this much per building</p> <p>Total gas saving: 454,055 Kwh</p> <p>Total electricity saving: 253,123 Kwh</p> <p>Previous Audits have shown projects cost about £492 per tonne</p>

Carbon Management Plan

working with

**Project definition**

Reference	Boilers
Title	Oil to gas boiler Conversion
Description	Replace 16 oil boilers to natural gas
Owner	Elwyn Rowlands
Directorate / team	BMU
Director responsible	Andy Farrell
Date submitted	9th January

**Carbon savings**

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Gas oil	421,676	litres/yr	4,387,847	1,213,327
Carbon source 2:	Natural gas (kWh)	-4,130,711	kWh/yr	-4,130,711	-759,886

Data quality: Estimates

Quantification method: Like for Like swaps based on KWH

**Financial**

Capital cost	£0
Annual operating cost	£0
Gross annual savings	£95,471
Net annual savings	£95,471
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	0.0

**Risk assessment**

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified

**Project status and next steps**

Overall status	Red
Current status of data	Estimated costs
Enabling actions to change status	Source finance

Carbon Management Plan

working with

**Project definition**

Reference	Boilers 2
Title	Oil to biomass boiler Conversion
Description	Replace 3 oil boilers to biomass in those buildings that don't have gas supplies already
Owner	Elwyn Rowlands
Directorate / team	Env and Regen
Director responsible	Andy Farrell
Date submitted	18th January 2011

**Carbon savings**

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Gas oil	103,750	litres/yr	1,079,595	298,529
Carbon source 2:	Wood	-342	tonnes/yr	-1,016,581	-25,415

Data quality: Estimates

Quantification method: Like for Like swaps based on KWH

**Financial**

Capital cost	£30,000
Annual operating cost	£0
Gross annual savings	£27,935
Net annual savings	£27,935

Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	1.1

Just ba:

**Risk assessment**

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified

**Project status and next steps**

Overall status	Red
Current status of data	Estimated costs
Enabling actions to change status	Seek Finance and source biomass supplier

### Project definition

Reference	41
Title	Cavity and loft insulation for schools
Description	Improving the cavity and loft insulation of our schools. We have estimated that half of our schools estate would need significant improvement
Owner	Mark McGiveron
Directorate / team	Estates
Director responsible	Andy Farrell
Date submitted	20th January 2011

### Carbon savings

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Natural gas (kWh)	2,997,442	kWh/yr	2,997,442	551,409
Carbon source 2:					

Data quality: Estimates

Quantification method: Estimates from RAP tool and cost based on cost of insulation per m<sup>2</sup> of a current quote for insulating high school

### Financial

Capital cost	£1,004,498
Annual operating cost	
Gross annual savings	£62,946
Net annual savings	£62,946
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	16.0

### Risk assessment

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified
Finance: Operational expense	Medium			

### Project status and next steps

Overall status	Red
Current status of data	RAP tool estimate
Enabling actions to change status	Look at finance options Get accurate quote - likely to come in lower if a large scheme was tendered.

### Project definition

Reference	42
Title	Bus Interchange Lighting Replacement
Description	As above
Owner	Tony Cross
Directorate / team	Transport
Director responsible	Andy Farrell
Date submitted	19 January 2011

### Carbon savings

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Electricity (grid)	53,845	kWh/yr	53,845	29,435
Carbon source 2:					

Data quality: Estimates

Quantification method: Estimates given from site survey by company in 2009

### Financial

Capital cost	£46,000
Annual operating cost	
Gross annual savings	£5,385
Net annual savings	£5,385
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	8.5

### Risk assessment

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified
New survey yields longer payback period	High	None identified	Medium	Dependent on funded

### Project status and next steps

Overall status	Red
Current status of data	Estimated costs
Enabling actions to change status	Get survey re-done with new Estimates

<b>Project:</b>	<b>Dedicated Schools resource</b>
<b>Reference:</b>	43
<b>Owner (person)</b>	Hilary Smith & Rachel Waggett
<b>Department</b>	Children and Young Peoples Services and Environment and Regeneration
<b>Description</b>	Identify a dedicated resource to spend time purely with schools on engagement and behaviour change.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £106,967</li> <li>• Payback period: 0 years</li> <li>• CO<sub>2</sub> Emissions reduction: 674</li> <li>• Targeting largest single carbon emission area within WBC footprint.</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost, e.g. the initial cost of implementing the project</li> <li>• £26,285 per year</li> <li>• Funding yet to be identified</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• To ensure savings are realised, dedicated support needs to be identified, to support schools in a coherent and long term strategy of energy awareness and behaviour change.</li> <li>• Will build on the current school's engagement programme therefore the delayed start for project.</li> <li>• Will be dependent on the council's financial situation and recruiting or commissioning state in 2 years time, will need to review periodically. This resource could be identified from within the council or an external resource.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Number of schools engaged with, individual projects delivered and carbon savings being realised.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ start date: April 2013</li> <li>○ completion date (when it will deliver savings): April 2014</li> </ul> </li> </ul> <p>A later start date for this project enables us to finish and implement the projects from the current audit programs and pilot schools engagement.</p>
<b>Notes</b>	<p>Based on a 5 % reduction of schools fossil fuel and electricity consumption</p> <p>Based on a Grade 6 officer plus on costs – based on similar graded engagement posts</p>

## Business travel – 34

The package of business travel options contains a number of different proposals which are outlined over the next few pages

<b>Project:</b>	Ways to Travel
<b>Reference:</b>	34
<b>Owner (person)</b>	Stephen Hunter / Ben Logan
<b>Department</b>	Transport, Engineering, Climate Change / People and Improvement
<b>Description</b>	Looking at the way staff travel will be split into a number of programs. This element of the program looks at awareness raising of travel alternative through a web travel portal, that will highlight travel alternatives. The other element will be a policy to be issued and enforced by managers across all directorates that gets staff to reduce their car travel modes.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>CO<sub>2</sub> Emissions reduction: 5 % of business travel for the travel portal and 10% for the enforcement of alternative travel. 102 tonnes</li> <li>Financial savings to be measured</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>Travel portal development is being developed and funded through the Cheshire and Warrington public sector carbon management group.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>The projects will be delivered from staff within smarter choices, climate change and people and improvement</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>The key issue with this program will be ensuring that there is buy in from the very top, otherwise managers lower down will not be motivated to enforce travel policy.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Reduction in car business mileage and flights will show success. As will the monitoring of bicycle users, IT technology and train travel.</li> <li>Travel will be monitored yearly.</li> </ul>
<b>Timing</b>	Start work: April 2011 Deliver savings: from October 2011



working with



Carbon Management Plan

<b>Project:</b>	<b>Pool Bus Pass</b>
<b>Reference:</b>	34
<b>Owner (person)</b>	Stephen Hunter
<b>Department</b>	Transport, Engineering and Climate Change
<b>Description</b>	Annual bus pass available to be used by all staff in New Town House and Quattro, can be booked in the same way as pool cars.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>Financial savings: £670 per year</li> <li>Payback period: 1 year</li> <li>CO<sub>2</sub> Emissions reduction: 5 tonnes</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>Project cost: £460 for an annual network bus pass</li> <li>Source of funding: Internal Travel Budgets</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>Booking will be managed by Business Support, useage will be monitored by smarter choices team</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>Making sure the pass is utilised through promotion and awareness is key.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>Number of miles travelled with the bus pass is comparable to a reduction in business mileage</li> </ul>
<b>Timing</b>	Purchase Pass: April 2011 Monitor usage and report back April 2012



<b>Project:</b>	<b>Pool bikes &amp; cycle training</b>
<b>Reference:</b>	34
<b>Owner (person)</b>	Lesley McAllister
<b>Department</b>	Strategic Transportation
<b>Description</b>	The provision, management, maintenance and promotion of a pool of bicycles for short business journeys to reduce the need to bring and use car for work, and training for staff to ensure safety and competency.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: savings cost of car mileage 65p/mile</li> <li>• Payback period: Year 1 onwards</li> <li>• CO<sub>2</sub> Emissions reduction: as part of package</li> <li>• Healthier workforce</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost - £1400</li> <li>• Operational costs - £400 per annum maintenance &amp; £200 per annum training costs</li> <li>• Source of funding: Unknown at present</li> <li>• Internal decision on funding between Jan &amp; March 2011</li> </ul>
<b>Resources</b>	Can be delivered by current resources (Smarter Choices team)
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Funding stream to be made available for purchase and maintenance of bikes and training of staff.</li> <li>• Principal risks:- Bikes fall into disrepair due to lack of maintenance funding, strong management line to ensure bikes are considered and used for short journeys.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Measure - no. and length of car journeys replaced by cycling.</li> <li>• Measured monthly/annually</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ Poss start date: 01/04/2011</li> <li>○ completion date (when it will deliver savings): 01/04/2012</li> <li>○ interim deliverable / decision points 01/10/2011</li> </ul> </li> </ul> <p>You could also lay these out as a milestone chart for ease and clarity. Break the timescale down into a handful of milestone points so progress can be measured</p>
<b>Notes</b>	<p>Explain sources used for quantification</p> <p>Any further notes that will help the reader understand the project/initiative.</p>

<b>Project:</b>	<b>Staff Travel Survey</b>
<b>Reference:</b>	34
<b>Owner (person)</b>	Lesley McAllister
<b>Department</b>	Strategic Transportation
<b>Description</b>	A survey of all staff to determine current mode of travel to and for work and what will be required to change and reduce car use.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Enables measurement of current and future travel habits</li> <li>• Identifies additional measures needed to enable change</li> <li>• Raises awareness.</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost – staff time (Smarter Choices, IT &amp; communications)</li> <li>• Internal decision by end March 2011</li> </ul>
<b>Resources</b>	Can be delivered by current resources
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Strong senior management line to ensure completion.</li> <li>• Principal risks:- non-completion of questionnaire by staff</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Measure – high percentage of completion.</li> <li>• On completion, and every two years.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ Poss start date - August 2011</li> <li>○ completion date - August 2011</li> <li>○ Reporting – October 2011</li> </ul> </li> </ul>
<b>Notes</b>	<p>Explain sources used for quantification</p> <p>Any further notes that will help the reader understand the project/initiative.</p>

## Fleet

### Project definition

Reference	Fleet
Title	Fleet electric courier vehicle
Description	Replacement of diesel vehicle with electrically fuelled vehicle.
Owner	Rachel Waggett/Dave Smith
Directorate / team	Climate Change
Director responsible	Andy Farrall
Date submitted	20th January 2011

### Carbon savings

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Diesel	11,016	litres/yr	110,425	27,935
Carbon source 2:					

Data quality: Actual

Quantification method: Data from emissions of vehicle to be replaced by electric vehicle.

### Financial

Capital cost	£29,000
Annual operating cost	
Gross annual savings	£12,075
Net annual savings	£12,075
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	10
Payback period (years) *	2.4

### Risk assessment

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Operational expense	Medium	Maintenance contract for 2 years included in purchase price.	High	None identified

### Project status and next steps

Overall status	Green
Current status of data	Estimated costs

<b>Project:</b>	<b>Fleet Telematic System</b>
<b>Reference:</b>	35
<b>Owner (person)</b>	David Smith
<b>Department</b>	Fleet Services
<b>Description</b>	The required system will be a real time web based vehicle and plant telematics and tracking system. Scope of the requirements fall into three main categories of asset tracking, telematics and data reporting.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £ 58,043</li> <li>• Payback period: 1.2 years</li> <li>• CO<sub>2</sub> Emissions reduction: 133.9 tonnes of CO<sub>2</sub></li> <li>• Multiple benefits should be derived from the introduction of the system inclusive of;                             <ul style="list-style-type: none"> <li>○ Fuel savings</li> <li>○ Greater fleet efficiency through improved utilisation</li> <li>○ Improved customer service</li> </ul> </li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Purchase Cost: Estimated cost of £1,000 per unit, estimated cost £70,000</li> <li>• Operational Cost: Data charges estimated to be £25 per month per unit.</li> <li>• Source of funding: Waste Capital Programme</li> <li>• Decision on capital already made currently out to tender.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Project will be delivered within current resources. Selected supplier providing additional resource during installation and launch.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Key success factors: Data analysis is key with results forming part of the decision making process for fleet efficiencies.</li> <li>• Principal risks: Expectation of system requirements are not fully met by supplier base. Anticipated efficiencies are not fully achieved.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Operational KPI's. Increased fleet utilisation. Reduction in fuel usage.</li> <li>• Monthly performance indicators and annual analysis of fuel spend.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ Invitation to tender December 2010</li> <li>○ Contract award: March 2011</li> </ul> </li> </ul>
<b>Notes</b>	Based on a 10% fuel saving for 70% of the fleet.

<b>Project:</b>	<b>Fleet Replacement Strategy of RCV's</b>
<b>Reference:</b>	44
<b>Owner (person)</b>	David Smith
<b>Department</b>	Fleet Services
<b>Description</b>	Delivery of a fleet replacement strategy for refuse vehicles. Strategy is to maintain a maximum 7 year asset life through replacing 5 vehicles per annum progressing to an in life position by 2015. Current position of fleet is 44% out of life with 28% being 14 years old.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £ 161,207</li> <li>• CO<sub>2</sub> Emissions reduction: 373 tonnes of CO<sub>2</sub></li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £700,000 per annum.</li> <li>• Operational costs: Reduced operational costs from current position in addition to increased operational efficiency.</li> <li>• Source of funding: Capital funding bid.</li> <li>• Funding decision: Budget finalisation Feb 2011.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Additional resource: No additional resource is anticipated. Current internal Fleet Services / VMU resources will be utilised to deliver the replacement programme as part of a wider fleet replacement strategy.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Key success factors: Capital budget approval.</li> <li>• Principal risks: Capital budget approval is declined.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Metrics for displaying performance: Age profile of fleet.</li> <li>• <b>When success will be measured / evaluated:</b> Annually within reporting structure.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                             <ul style="list-style-type: none"> <li>○ start date: 01/04/2011</li> <li>○ completion date (when it will deliver savings): On going with savings achieved from point of delivery of new and removal of old assets from fleet.</li> </ul> </li> </ul>
<b>Notes</b>	Using an estimate based on the Carbon Trusts RAP tool for 85% of the refuse fleet

## Waste

<b>Project:</b>	<b>Corporate Waste Minimisation Strategy and implementation</b>
<b>Reference:</b>	37
<b>Owner (person)</b>	Paul McHenry
<b>Department</b>	Waste Management
<b>Description</b>	<p>Develop and implement an authority wide waste minimisation strategy and action plan. This strategy would cover all the authority’s waste streams and would be developed in line with moving towards more desirable and sustainable elements of the Waste Hierarchy. This would mean the maximisation of recycling and the reuse and reduction of all waste whenever possible.</p> <p>Examples of actions would include: waste education of all staff, increase office recycling, maximise reuse and recycling of waste through all new contracts and projects, procure recycled content items whenever possible, expand green team members to help promote waste minimisation and reduce and compost bio-degradable waste.</p>
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings:</li> <li>• <b>Long term waste disposal cost savings to all departments</b></li> <li>• CO<sub>2</sub> Emissions reduction:</li> <li>• <b>Increased CO<sub>2</sub> reduction the more we reduce, reuse and recycle our waste over sending waste to landfill or incineration. Estimated at 5% of waste emissions due to uncertainties – 31.7 tonnes</b></li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• The strategy would be developed with a minimal budget.</li> <li>• However the implementation of the plan would require funding from all departments, especially when looking at providing additional recycling facilities. A small budget would be required to promote the scheme to staff.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Staff time from the waste minimisation and recycling team and climate change officer</li> <li>• Staff time from all departments to help implement changes.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Key factors to success include: Buy-in from all departments and commitment from staff on all sites.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Waste tonnage from each building and levels of recycling (%) will be monitored and recorded and published at the end of each year. This will allow the calculation of CO<sub>2</sub> reductions year on year.</li> <li>• A review of the strategy and its achievements would be provided every two years.</li> </ul>
<b>Timing</b>	Draft Corporate Waste Minimisation Strategy to be produced by March 2011 for consultation.

## Water

### Project definition

Reference	Water 1
Title	Save a Flush
Description	Reduce water consumption by 3% by installing save a flush into all toilets
Owner	Laura Stanley
Directorate / team	Climate Change
Director responsible	Andy Farrell
Date submitted	03 September 2010

### Carbon savings

	Type of carbon source	Abated annual quantity	Units	Conversion to kWh/year (or tonnes for waste, or m <sup>3</sup> for water)	Carbon savings (kgCO <sub>2</sub> /yr)
Carbon source 1:	Water	6,284	m3/yr	6,284	2,539
Carbon source 2:					

Data quality: Estimates

Quantification method: Method is based on average calculations from utility companies and save a flush information.

### Financial

Capital cost	£2,000
Annual operating cost	
Gross annual savings	£12,819
Net annual savings	£12,819
Project start year	2011
Year of first savings	2012
Lifetime of project (years)	20
Payback period (years) *	0.2

### Risk assessment

Risk item	Probability	Steps to minimise probability	Impact	Steps to minimise impact
Finance: Lack of capital investment	Medium	Look to identify existing capital budget. Seek	High	None identified
Resources: Staff time during feasibility &	Medium		Low	

### Project status and next steps

Current Status of Project	Estimated costs
Enabling Actions to Change Status	- Gain finance approval - Liaise with building managers for implementation

## Street Lighting

<b>Project:</b>	<b>Street Lighting Bollard Replacement</b>
<b>Reference:</b>	45
<b>Owner (person)</b>	Dave Vasey
<b>Department</b>	Transportation, Engineering & Climate Change
<b>Description</b>	Part 1 Replacement of remaining illuminated bollards with non illuminated & Solar Powered Qty 500 No
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £15,314 per annum</li> <li>• Payback period: 6.9 years</li> <li>• CO<sub>2</sub> Emissions reduction: 83tonnes</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £106,000</li> <li>• No funding source has been identified to date.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Existing design staff</li> <li>• Additional funding will be required for labour &amp; materials to carryout the replacement of the remaining Bollards.</li> </ul>
<b>Ensuring Success</b>	<ol style="list-style-type: none"> <li>a) Brief Portfolio Member</li> <li>b) Identify funding</li> </ol>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Outcomes will be measured by comparing the estimated reduction in energy consumption and Carbon Emissions with the actual.</li> <li>• When success will be measured / evaluated Two months following the completion of the project</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                         <ul style="list-style-type: none"> <li>○ start date: Dependant on funding</li> <li>○ completion will be 6 months following implementation</li> <li>○ interim deliverable / decision points</li> </ul> </li> </ul>
<b>Notes</b>	<p>Explain sources used for quantification The quantification of this project is based on energy consumption calculated by nationally agreed criteria and industry standards</p> <p>Capital expenditure is based on current market material &amp; labour costs</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p>



<b>Project:</b>	<b>Street Lighting Lantern Change Mercury Vapour Lamps</b>
<b>Reference:</b>	46
<b>Owner (person)</b>	Dave Vasey
<b>Department</b>	Transportation, Engineering & Climate Change
<b>Description</b>	Replacement of old street lanterns which are both inefficient in terms Energy Consumption and Light Output. Qty 1300 No
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £31,283 per annum</li> <li>• Payback period: 3.7 years</li> <li>• CO<sub>2</sub> Emissions reduction: 170 tonnes</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £117,000</li> <li>• No funding source has been identified to date.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Existing design staff</li> <li>• Additional funding will be required for labour &amp; materials to carryout the replacement of the remaining Bollards, this is detailed in the attached breakdown.</li> </ul>
<b>Ensuring Success</b>	<ol style="list-style-type: none"> <li>a) Brief Portfolio Member</li> <li>b) Identify funding</li> </ol>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Outcomes will be measured by comparing the estimated reduction in energy consumption and Carbon Emissions with the actual.</li> <li>• When success will be measured / evaluated Two months following the completion of the project.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                         <ul style="list-style-type: none"> <li>○ start date: Dependant on funding</li> <li>○ completion will be 1 months following implementation</li> <li>○ interim deliverable / decision points</li> </ul> </li> </ul>
<b>Notes</b>	<p>Explain sources used for quantification The quantification of this project is based on energy consumption calculated by nationally agreed criteria and industry standards</p> <p>Capital expenditure is based on current market material &amp; labour costs</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p>

<b>Project:</b>	Street Lighting Part Night Operation
<b>Reference:</b>	47
<b>Owner (person)</b>	D Vasey
<b>Department</b>	Transportation, Engineering & Climate Change
<b>Description</b>	Part 1 Conversion of lighting units to part night, where nighttime activity low or no activity takes placed after certain times. Qty 34
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £311 per annum</li> <li>• Payback period: 0 years</li> <li>• CO<sub>2</sub> Emissions reduction: 1.7 tonnes per annum</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £0</li> <li>• No funding source has been identified to date.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Existing design staff</li> <li>• Additional funding will be required for labour &amp; materials to carryout the replacement of the remaining Bollards, this is detailed in the attached breakdown.</li> </ul>
<b>Ensuring Success</b>	<ol style="list-style-type: none"> <li>a) Risk assessment or each location to be completed</li> <li>b) Brief Portfolio Member</li> </ol>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Outcomes will be measured by comparing the estimated reduction in energy consumption and Carbon Emissions with the actual.</li> <li>• When success will be measured / evaluated Two months following the completion of the project.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.                         <ul style="list-style-type: none"> <li>○ start date: Dependant on funding</li> <li>○ completion will be 1 months following implementation</li> <li>○ interim deliverable / decision points</li> </ul> </li> </ul>
<b>Notes</b>	<p>Explain sources used for quantification The quantification of this project is based on energy consumption calculated by nationally agreed criteria and industry standards</p> <p>Capital expenditure is based on current market material &amp; labour costs</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p>

<b>Project:</b>	Street Lighting Column Switch Off
<b>Reference:</b>	48
<b>Owner (person)</b>	D Vasey
<b>Department</b>	Transportation, Engineering & Climate Change
<b>Description</b>	<p>Part 1 Removal of street lighting columns on footpaths immediately adjacent existing road lighting where the road lighting is considered to be sufficient to meet the needs of the area.</p> <p>Part 2 Removal of street lighting columns where the use of the road has changed eg: Stopped Up and lighting is no longer required..</p>
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £1,263 per annum</li> <li>• Payback period: 0 years</li> <li>• CO<sub>2</sub> Emissions reduction: 6.9 tonnes per annum</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £0</li> <li>• No funding source has been identified to date.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Existing design staff</li> <li>• Additional funding will be required for labour &amp; materials to carryout the replacement of the remaining Bollards, this is detailed in the attached breakdown.</li> </ul>
<b>Ensuring Success</b>	<p>a) Risk assessment or each location to be completed</p> <p>b) Brief Portfolio Member</p>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Outcomes will be measured by comparing the estimated reduction in energy consumption and Carbon Emissions with the actual.</li> <li>• When success will be measured / evaluated Two months following the completion of the project.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g.             <ul style="list-style-type: none"> <li>○ start date: Dependant on funding</li> <li>○ completion will be 1 months following implementation</li> <li>○ interim deliverable / decision points</li> </ul> </li> </ul>
<b>Notes</b>	<p>Explain sources used for quantification</p> <p>The quantification of this project is based on energy consumption calculated by nationally agreed criteria and industry standards</p> <p>Capital expenditure is based on current market material &amp; labour costs</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p>

<b>Project:</b>	Street Lighting Sign Lantern Replacement
<b>Reference:</b>	49
<b>Owner (person)</b>	Dave Vasey
<b>Department</b>	Transportation, Engineering & Climate Change
<b>Description</b>	Part 1 Replacement of remaining sign lanterns to LED light source Qty 500 No
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £26,089 per annum</li> <li>• Payback period: 4.4 years</li> <li>• CO<sub>2</sub> Emissions reduction: 142 tonnes</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Project cost: £115,000</li> <li>• No funding source has been identified to date.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Existing design staff</li> <li>• Additional funding will be required for labour &amp; materials to carryout the replacement of the remaining Bollards, this is detailed in the attached breakdown.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>a) Brief Portfolio Member</li> <li>b) Identify funding</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Outcomes will be measured by comparing the estimated reduction in energy consumption and Carbon Emissions with the actual.</li> <li>• When success will be measured / evaluated Two months following the completion of the project.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Milestones / key dates e.g. <ul style="list-style-type: none"> <li>○ start date: Dependant on funding</li> <li>○ completion will be 5 months following implementation</li> <li>○ interim deliverable / decision points</li> </ul> </li> </ul>
<b>Notes</b>	<p>The quantification of this project is based on energy consumption calculated by nationally agreed criteria and industry standards</p> <p>Capital expenditure is based on current market material &amp; labour costs</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p> <p>Street lighting projects of this nature have previously been audited and approved by Salix demonstrating that they offer true energy efficiencies and are deliverable</p> <p>Any further notes that will help the reader understand the project/initiative.</p>

## Renewable Technologies

<b>Project:</b>	<b>Warrington Solar Farm</b>
<b>Reference:</b>	50
<b>Owner (person)</b>	Dave Cowley and Andy Doyle
<b>Department</b>	Environment & Regeneration
<b>Description</b>	It is proposed to develop a free-standing solar photovoltaic system on currently unused land in Warrington. The system will be designed to minimise impact on surroundings and the local community. It will also be designed to allow other sustainable site uses including farming and agriculture.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial income : Depending on timing of implementation the financial income is estimated at £31.3m or £28.9m over 25 years</li> <li>• Capital cost estimated at £10m with £3m operating and maintenance costs</li> <li>• Payback period: 25 years</li> <li>• CO<sub>2</sub> Emissions reduction: 2040 tonnes per year</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Prudential borrowing repaid by feed in tariff.</li> <li>• Operational costs will be included within this funding assessment.</li> <li>• Source of funding: to be determined</li> <li>• A decision on a project of this magnitude will be made at Executive level, likely to be approximately November 2011.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Additional resource is required from legal and other advisors. This cost will be factored into the funding assessment.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• It will be essential to have the support and buy-in of local ward councillors and communities for this important landmark project.</li> <li>• Learning lessons from other proposed and installed solar systems of this size will reduce risk.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Output from system in terms of energy and financial benefit.</li> <li>• Annually at financial year end.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Estimated milestones / key dates                             <ul style="list-style-type: none"> <li>○ Agreement to proceed with initial investigations: February 2011</li> <li>○ All agreements in place to procure system: November 2011</li> <li>○ start date: March 2012</li> <li>○ completion date (when it will deliver savings): June 2012</li> </ul> </li> </ul>
<b>Notes</b>	<ul style="list-style-type: none"> <li>▪ Annual energy generation = 750 kWh/kWp</li> <li>▪ Assuming an installation of 5 MW, then estimated energy generation is 5,000 x 750 = 3,750,000 kWh/yr</li> <li>▪ Assuming CO<sub>2</sub> at 0.544kg/kWh, carbon saved will be 2040 tonnes/year</li> </ul>

<b>Project:</b>	<b>Orford Community Sports Hub – PV roof array</b>
<b>Reference:</b>	51
<b>Owner (person)</b>	Ian Lamb
<b>Department</b>	Planning & Regeneration
<b>Description</b>	<p>The new Orford Park Community Sports Hub will contain community facilities including library, meeting and lecture rooms, café and informal socialising space, swimming pool, health and fitness centre, dance studios, squash courts, a sports hall and crèche facilities. There will also be considerable new outdoor space including playing fields, skateboarding and BMX facilities, play areas, bowling greens and dog walking areas.</p> <p>This project proposes the installation of photovoltaic panels on the roof of the building which will operate to provide electricity to the building and will feed energy to the grid if not used by the building. The panels will be installed during the construction phase, minimising installation cost.</p> <p>The roof area of the building is 2,800m<sup>2</sup> however considerable allowance needs to be made for roof mounted plant. Therefore the area assumed to be used for photovoltaic installation is 1,400m<sup>2</sup>.</p>
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• An estimated 138,600kWh electricity would be generated by the array. The majority of this is likely to be used within the building given the extended opening hours and range of uses. Estimated savings in electricity costs alone £13,860.</li> <li>• Estimated carbon savings 74.84 tonnes per year.</li> <li>• Promotion of the energy efficiency characteristics of the building due to the highly visible nature of the PV system.</li> <li>• Use as a learning tool given that the building will be used by the community and by William Beamont School pupils for sports activity.</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Estimated installed cost based on Carbon Trust benchmark figures £700,000 for 1400m<sup>2</sup>. This is likely to be sourced from prudential borrowing which would be repaid using revenue from Feed In Tariff income.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• As the building is under construction, the design team and project team can carry out this project using current resource.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• Funding constraints will be the main barrier to the success of this project.</li> <li>• Planning amendment will need to be made.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Measuring energy performance in early years of occupation.</li> <li>• Year one, two and three following occupation.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>○ start date: Start on site October 2010</li> <li>○ completion date (when it will deliver savings): January 2012</li> </ul>
<b>Notes</b>	<p>Assumptions as below:</p> <p>Typical output 132 Wp/m<sup>2</sup> (average of published figures for UK)</p> <p>750 kWh/kWp for well sited PV in the UK.</p> <p>0.54kgCO<sub>2</sub>/kWh</p>

<b>Project:</b>	<b>Schools Solar Project</b>
<b>Reference:</b>	52
<b>Owner (person)</b>	Rachel Waggett
<b>Department</b>	Children and Young Peoples services
<b>Description</b>	Taking the opportunity of feed in tariffs and ensuring as many schools as possible have solar power PV panels on their roofs.
<b>Benefits</b>	<ul style="list-style-type: none"> <li>• Financial savings: £145,728 per year excluding feed-in tariffs</li> <li>• Payback period: Would need to be quantified in line with return from feed-in tariffs. Will be most relevant to calculate for individuals schools. The Financial saving and emissions reduction are based on estimates</li> <li>• CO<sub>2</sub> Emissions reduction: 793</li> </ul>
<b>Funding</b>	<ul style="list-style-type: none"> <li>• Estimated cost of project is £4,887,745 excluding the cost of borrowing.</li> <li>• Funding is currently being discussed with a view to assessing available options.</li> <li>• Operational costs will be included within this funding assessment.</li> <li>• Source of funding: to be determined</li> <li>• A decision on a project of this magnitude will be made at Executive level.</li> </ul>
<b>Resources</b>	<ul style="list-style-type: none"> <li>• Additional resource is required from legal and other advisors. This cost will be factored into the funding assessment.</li> </ul>
<b>Ensuring Success</b>	<ul style="list-style-type: none"> <li>• It will be essential to have the support and buy-in of local ward councillors and school head teachers..</li> <li>• Learning lessons from schools that have delivered this before will reduce risk.</li> </ul>
<b>Measuring Success</b>	<ul style="list-style-type: none"> <li>• Output from systems in terms of energy and financial benefit.</li> <li>• Annually at financial year end in line with carbon footprint reporting.</li> </ul>
<b>Timing</b>	<ul style="list-style-type: none"> <li>• Estimated milestones / key dates                             <ul style="list-style-type: none"> <li>○ Start looking at feasibility of this program September 2011</li> </ul> </li> </ul>
<b>Notes</b>	<ul style="list-style-type: none"> <li>○ Assuming an installation on every school in the borough that will produce - 1,457,280 kWh/yr in line with the calculations for the solar farm.</li> <li>○ Assuming CO<sub>2</sub> at 0.544kg/kWh, carbon saved will be 793 tonnes/year</li> </ul>



Warrington Borough Council

New Town House, Butermarket Street  
Warrington  
WA1 1BN

Tel: 01925 444400

[www.warrington.gov.uk](http://www.warrington.gov.uk)